6) CONTOUR INTERVAL: 2 FOOT TOPOGRAPHIC INFORMATION WAS PROVIDED BY WIKLE LAND SURVEYING, P.C., ELEVATIONS ARE MEAN SEA LEVEL.

7) ALL CONSTRUCTION SHALL CONFORM TO THE CHEROKEE COUNTY DEVELOPMENT REGULATIONS, LATEST EDITION.

REGULATIONS, LATEST EDITION.

8) SOME UNDERGROUND UTLITIES AND/OR STRUCTURES MAY NOT BE SHOWN. THE EXACT SIZE
AND LOCATION OF ALL UTILITIES SHOWN OR NOT SHOWN SHALL BE THE RESPONSIBILITY OF THE
CONTRACTOR TO DETERMINE PRIOR TO CONSTRUCTION.
9) CONTRACTOR SHALL VERIFY ALL QUANTITIES AND DIMENSIONS.

10) A COPY OF THE APPROVED GRADING PLAN MUST BE ON THE JOB SITE AT ALL TIMES THAT CONSTRUCTION IS UNDERWAY.

11) PERMISSION MUST BE OBTAINED FROM ANY ADJACENT PROPERTY OWNER WHOSE LAND MAY BE AFFECTED FROM CONSTRUCTION NEAR PROPERTY LINES.

BE AFFECTED FROM CONSTRUCTION NEAR PROPERTY LINES.
12) GRASS ALL DISTURBED AREAS IMMEDIATELY UPON COMPLETION OF WORK.
13) IF SILT COLLECTS WITHIN ONE FOOT OF THE TOP OF THE BARRIER THE SILT SHOULD BE REMOVED, SEDMENT BARRIERS SHOULD BE INSTALLED PRIOR TO START OF WORK TO INSURE PROPER EROSION & SEDMENT CONTROL. SEDMENT CONTROL MEASURES SHOULD BE INSPECTED AFTER EACH STORM EVENT.

14) ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE CHECKED DAILY AND DEFICIENCIES NOTED WILL BE CORRECTED BY THE END OF EACH DAY. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED IF DEEMED NECESSARY BY ON SITE INSPECTION.
15) SILT FENCES SHALL BE REINFORCED AT LOW POINTS.

16) SEDIMENT CONTROL STRUCTURES SHALL BE INSTALLED AS THE FIRST ITEM OF THE CONSTRUCTION

CONSTRUCTION

1.7) IN OUR OPINION THE ONLY WELL LOCATED ON OR WITHIN 100' OF THE EXTERNAL BOUNDARY,
IS DELINEATED, HOWEVER THIS IS NOT CERTIFIED. 18) UTILITIES PROTECTION : 1-800-282-7411.

REFERENCE AND WILL

19) ALL INFORMATION SHOWN WITHIN RIGHT-OF-WAY IS FOR VISUAL

BE COMMENTED AND CONFORM TO GEORGIA D.O.T. SPECIFICATIONS.
20) CHANGES IN THE CONSTRUCTION PLANS OF STORM DRAINAGE FACILITIES CAUSED BY FIELD CONDITIONS SHALL BE MADE IN COMPLIANCE WITH SECTION 3.02-G OF THE CHEROKEE COUNTY

21) ALL METAL PIPE SHALL BE FULLY COATED OR ALUMINIZED.

22) SIGNAGE SHALL BE PERMITTED THROUGH CHEROKEE COUNTY PLANNING AND ZONING

23) CLEARING LIMITS, NOT TO EXCEED 17 ACRES AT ONE TIME. PAGE 10 SOIL. SEDIMENTATION. CONTROL ORDINANCE 2004-0-002.

24) Approval of these plans does not constitute approval by Cherokee County of any land disturbing activities within wetland areas. It is the responsibility of the property owner to co the appropriate regulatory agency for approval of these plans prior to undertaking any land

25) Approval of these plans does not constitute approval by Cherokee County of any land disturbing activities that may impact any federally-listed threatened or endangered species protected by the Endangered Species Act. It is the responsibility of the property owner to contact the US Fish and Wildlife Service for approval of these plans prior to undertaking any

28) NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN 25 OR 50 FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25 FT OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTION DETERMINATION LINE WITHOUT FIRST REQUIRING THE NECESSARY VARIANCES AND PERMITS.

27) IT IS OUR OPINION THAT NO STREAM BUFFER VARIANCES ARE NEEDED FOR THIS DEVELOPMENT

28) ALL WETLANDS OR STATE WATERS ON OR WITHIN 200 FEET OF THIS PROJECT HAVE BEEN

28) ALL WETLANDS OR STATE WATERS ON OR WITHIN 200 FEET OF THIS PROJECT HAVE BEEN DELINEATED.
29) RETAINING WALL DESIGN SHALL BE CERTIFIED BY A PROFESSIONAL ENGINEER CURRENTLY REGISTERED IN STATE OF GEORGIA. THIS DESIGN MUST BE SUBMITTED WITH THE CONSTRUCTION PLANS. INSPECTION AND CERTIFICATION BY SAID DESIGN PROFESSIONAL IS REQUIRED. (OR) A NOTE ON PLANS THAT NO RETAINING WALLS WILL BE CONSTRUCTED. NONE PLANNED AT THIS TIME 30) ALL CUTS IN PAYEMENT AND PAYEMENT EGGES ADJOINING NEW PAYEMENT SHALL BE SAW CUT. ALL RIGID PAVEMENT TO RIGID PAVEMENT SHALL B DOWELED WITH NO. 4 BARS SPACED

CÚT. ALL RIGID PAVEMENT TO RIGID PAVEMENT SHALL B DOWELED WITH NO. 4 BARS SPACED 12-INCHES ON CENTER AND GROUTED.

31) ALL PAVEMENTS STRIPING AND MARKINGS SHALL BE THERMOPLASTIC AS PER GEORGIA D.O.T. SPECIFICATION AND NOTED ON THE PLANS.

32) LIABILITY AND RESPONSIBILITY OF APPLICANT: THE APPLICANT IS RESPONSIBLE FOR THE RELOCATION, ADJUSTMENT OR REMOVAL OF ALL UTILITY CONFLICTS WITHIN THE DEVELOPMENT AREA AT NOT COST TO CHEROKEE COUNTY. THE COUNTY ENCOURAGES THE APPLICANT TO CONTACT THE UTILITIES PROTECTION CENTER (UPC) FOR "DESIGN LOCATE REQUESTS" WHICH AIDS IN THE LOCATION OF EXISTING UTILITY FACILITIES FOR PRE-DESINGN, ADVANCE PLANNING PURPOSES, ETC. EXCAVATORS SHALL CONTACT THE UPC IN ACCORDANCE WITH THE OFFICIAL CODE OF GEORGIA ANNOTATED 25.9, BEFORE COMMENCING EXCAVATION ACTIVITIES. 33) NO NEW STREETS ARE PLANNED FOR THIS DEVELOPMENT.

LÁNES, LET-TURN LANES ETC. CONSTRUCTED WITHIN THE COUNTY RIGHT OF WAY BECOMES FEATURES OF THE HIGHWAY AND THE UNCONDITIONAL PROPERTY OF THE BECOMES FEATURES OF THE HIGHWAY AND THE UNCONDITIONAL PROPERTY OF THE COUNTY. THE APPLICANT OR PROPERTY OWNER(S) AND/OR LESSES ADJACENT TO THE RIGHT OF WAY AT THE CROSSOVER SITE RETAIN NO OWNERSHIP OR LEGAL INTEREST THERIN. THE COUNTY RESERVES THE RIGHT AND AUTHORITY TO CLOSE, RELOCATE OR REMOVE A CROSSOVER WHEN SUCH ACTION IS DEEMED NECESSARY IN THE INTEREST OF THE PUBLIC SAFETY OR EFFICIENCY OF THE ROADWAY. WHEN DETERMINED NECESSARY BY THE COUNTY, ADDITIONAL RIGHT OF WAY FOR CONSTRUCTION AND PLACEMENT OF AUXILIARY LANES SHALL BE RELINQUISHED TO THE COUNTY (MINIMUM 13 EFFE ERGAL THE BACK OF CURP)

THE COUNTY (MINIMUM 13 FEET FROM THE BACK OF CURB). 35) Final grading of lots is not to alter natural drainage pattern. Flow shall enter and exit site as existing conditions unless written approval is obtained from lot owner and all downstream affected properties.

36) The proposed use and development of the subject site shall comply with the requirements of the Cherokee County Zoning Ordinance".

BY: WIKLE LAND SURVEYING, P.C. P.O. BOX 1164 CANTON, GEORGIA 30169 PHONE: (770) 479-8364 479-8364 SURVEYING AND MAPPING SOCIETY OF GEORGIA

CONSTRUCTION SCHEDULE

MOVE IN	CLEARING & GRUBBING	SILT FENCE & CONSTR. EXIT	GRADING	STORM & SEWER	INLET/OUTLET EROSION CONTROL	GRASSING TEMP. & PERM.	
WEEK 1	WEEK 1	WEEK 2	WEEK 2	WEEK 5	WEEK 1	WEEK 3	
	WEEK 2	COMPLETION	WEEK 4	WEEK 7	COMPLETION	COMPLETION	

MAINTENANCE OF S. & E. CONTROLS	CURB	UTILITIES	PAVING	FINAL LANDSCAPING & CLEARING	
WEEK 1	WEEK 4	WEEK 5	WEEK 6	WEEK 7	
COMPLETION	WEEK 5	WEEK 6	WEEK 7	COMPLETION	

NOTE: DATES ARE APPROXIMATE AND MAY VARY

THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO LAND-DISTURBING ACTIVITIES.

EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.

DISTURBED AREAS SHALL BE COVERED WITH TEMPORAY OR PERMANATE GROUND COVER IF LEFT MORE THAN 7 DAYS IT IS OUR OPINION THAT ALL STATE WATERS ON OR WITHIN 200' ARE SHOWN

CONSTRUCTION PLANS FOR: CHEROKEE 2

SITE ADDRESS 500 EAST ROPE MILL ROAD LAT 34.1473 / LONG -84.5089 @PROPOSED ENTRANCE

> TIN 15N15 074 PIN 15-0592-0001 PROJECT NUMBER PL2020000345 FIRE RMS 10381

NOTICE OF INTENT VERSION September 24, 2018 THESE PERMITS EXPIRE JULY 31, 2023 Trout Stream GLEN A NEDZA COUNTY CHARGE CRY CANTON SING GA L SITE/OWNER/OPERATOR INFORMATION 500 EAST ROPE MILL RD GREN NEDZA IL CONSTRUCTION SITE ACTIVITY INFORMATION AND FEE CALCULATORS

OWNER / DEVELOPER GLEN NEDZA 500 EAST ROPE MILL ROAD CANTON, GA 30115

TERTIARY PERMITTEE 24 hr. Contact: GLEN NEDZA PHONE: (404) 886–9502 EMAIL: gnedza2000@yahoo.com

POWER: GEORGIA POWER CO.1(888) 655-588 WATER: C.C.W.S.A. (770) 479-181	
SEWER: INDIVIDUAL SEPTIC (770) 479-044 PHONE: WINDSTREAM 1(800) 501-175	SEWER:

The contractor shall restore and replace any existing structures, utilities, trees, etc. that is not indicated in the contract documents to be removed. This items shall be replaced per appropriate or respective owner's satisfaction and standard specifications. All expenses incurred for this work and materials is

0

The contractor is responsible to coordinate with the respective utility owners before attempting any construction activities to any utilities or any

Contractor is responsible to obtain any required permits and/or approval from the respective utility owner prior to beginning any construction activities.

The contractor is responsible to allow access to all emergency vehicles at all

Under no circumstances shall the contractor's men or equipment encroach or block any driveways or entrances of the property or adjacent properties.

The contractor shall provide the necessary warning devices, signs, barricades, warning lights, etc. to adequately safely warn and control traffic at all times. All traffic control devises will be used on all work on this project in accordance with the Manual on Uniform Traffic Control Device current addition.

The contractor shall ensure that the site has positive drainage at all times away from the building.

The contractor shall locate and protect all utilities at all times. Any utilities damaged by the contractor, his equipment or men shall be replaced per respective owner's standards and specifications.

All retaining walls shall be designed by a Georgia registered engineer prior to any wall construction activity. The contractor shall include in his bid price the cost for all associated retaining wall design services.

Any existing utility structures that are within the limit of construction area and are to remain in place shall be raised or lowered to meet finish grade and/or raised or lowered to provide the required minimum cover. This work shall be done per respective utility company's standard specification and procedure.

ALL GRADES SHOWN ON THE PLANS INDICATES FINISH GRADES, UNLESS INDICATED

GENERAL CONSTRUCTION NOTES:

- 1) IRRIGATION SPRINKLERS ARE NOT ALLOWED IN THE ROAD RIGHT-OF-WAY. 2) MULCH OR TEMPORARY GRASSING SHALL BE APPLIED TO ALL EXPOSED AREAS WITHIN SEVEN (7) DAYS OF DISTURBANCE 6-33. 3) ALL SLOPES STEEPER THAN 2.5:1 AND WITH A HEIGHT OF 10' FEET OR
- I) ALL SLOPES STEEPER THAN 2.5:1 AND WITH A HEIGHT OF 10' FEET OR GREATER, AND CUTS AND FILLS WITHIN STREAM BUFFERS SHALL BE STABILIZED WITH APPROPRIATE EROSION CONTROL MATTING OR BLANKETS AND ACCORDING TO GEORGIA E.P.D. REQUIREMENTS.

 ALL EROSION CONTROL PONDS SHALL HAVE OUTLET STRUCTURE DETAILS WITH INVERT ELEVATIONS. AS BUILT PLANS SHALL SHOW ACTUAL AS BUILT ELEVATIONS ON INVERTS AND THE 100 YEAR FLOOD ELEVATION AT TOP OF PONDS OF CA D.O.T. TYPE C SILT FENCE SHALL BE INSTALLED ADJACENT DISTRIBUTED WATERS AND THE PROPERTY OF WATERS FROM ANY LAND AND ALL PROPERTY OF THE PROPERTY OF A BUINNING STREAM SHALL BE CONCEPTED ON ANY LAND ON A BUINNING STREAM SHALL BE CONCEPTED ON ANY LAND OF THE PROPERTY OF A BUINNING STREAM SHALL BE CONCEPTED ON AUTUALIAND OF THE PROPERTY OF THE PROPERTY OF A BUINNING STREAM SHALL BE CONCEPTED ON AUTUALIAND OF THE PROPERTY OF THE PROPERTY

- DISTURBING ACTIVITY.

 6) ALL PIPE IN A RUNNING STREAM SHALL BE CONCRETE OR ALUMINUM ALLOY.

 7) ALL CONSTRUCTION SHALL COMPLY WITH THE SPECIFICATIONS AND PROCEDURES
 DETAILED IN THE CURRENT DEVELOPMENT REQUIRED ATONS OF THE CHEROKEE COUNTY
 AND THE MANUAL FOR EROSION AND SEDMENT CONTROL IN GA.
- 8) UTILITIES, IF ANY, ARE TO BE UNDERGROUND INSTALLATION.
 9) ALL DRAINGAGE STRUCTURES SHALL BE BUILT ACCORDING TO DOT STANDARDS.

Any fill material supporting structural loads shall be engineered with proper documentation including Georgia Registered P.E. Stamp. Submit documentation the Cherokee County Building Department prior to foundation inspection.

2) Site development as-built drawings, containing a boundary survey, location, elevation, height, and square footage of building, parking areas, utilities, retaining walls, stormwater system, and any other pertinent site development data are required upon completion of this project. Cherokee County needs this information before site inspection for C.O. is issued, per ordinance # 2004-Z-001

INDEX DESCRIPTION

- 3) Temporary grassing or mulching is required every (7) seven days.
- 4) No grading within the undisturbed stream buffers or zoning buffers.
- 5) Wheel stops are needed for non-curbed parking

1) 2) 3) 4) 5) 6) 7) 8)	COVER SHEET EXISTING CONDITIONS SITE PLAN GRADING PLAN TREE PRESERVATION PLAN PHASE I EROSION PLAN PHASE II EROSION PLAN
8)	PHASE III EROSION PLAN
	EROSION NOTES
10)	EROSION DETAILS
11)	CONSTRUCTION DETAILS
12)	TREE DETAILS
13)	WATER DETAILS
14)	TRUCK MANEUVER PLAN
15)	ROAD PLAN
16)	FIRE PLAN
17)	DRAINAGE BASIN
18)	LIGHTING PLAN
19)	WALL DESIGN
20)	WALL NOTES

	REVISIONS
DATE	COMMENTS
4-01-21	REVISIONS PER COMMENTS
5-01-21	REVISIONS PER COMMENTS
8-10-21	REVISIONS PER COMMENTS

LAND LOT: 592 DISTRICT- 15, SECTION- 2 CHEROKEE COUNTY, GEORGIA

ENTRANCE 2 P&P

DRIVEWAY P&P

SHEET 1 OF 23 SHEETS

FIELD BOOK 52 ,PAGE 41 ,FILE R 1061. 1) I.P.S. — IRON PIN SET (#5 R.)
2) I.P.F. — IRON PIN FOUND
3) I.L.L. — LAND LOT LINE
4) R/W — RIGHT OF WAY
5) R — PROPERTY LINE
6) G — CENTER LINE
7) R. — REINFORCING BAR
8) P.P. — POWER &(OR) PHONE POLE
9) N./F. — NOW OR FORMERLY
10) ———— — FENCE (APPROX. OC.) -√w- - OVERHEAD UTILITY LINE 12) B.L. — BUILDING LINE 13) D.E. — DRAINAGE EASEMENT 14) S.S.E. — SANITARY SEWER EASEMENI 16) P.A.M.E. — POND ACCESS & MANAGEMENT EASEMENT 17) — TSW— — TREE SAVE FENCE THE FIELD DATA UPON WHICH THIS PLAT IS BASED HAS A CLOSURE PRECISION OF ONE FOOT IN 10,000+FEET AND AN ANGULAR ERROR OF 02" PER ANGLE POINT AND WAS ADJUSTED USING THE COMPASS RULE. THIS PLAT HAS BEEN CALCULATED FOR CLOSURE AND FOUND TO BE ACCURATE WITHIN ONE FOOT IN 100,000+ FEET. EQUIPMENT USED FOR MEASUREMENTS TOPCON GTS - 303, TOTAL STATION GRAPHIC SCALE - FEET

NOTES:

1) THIS PLAT IS SUBJECT TO ALL EASEMENTS AND RIGHTS—OF—WAY PRIVATE AND PUBLIC.

2) UNDERGROUND UTILITIES AND/OR STRUCTURES, IF ANY, MAY NOT BE SHOWN.

3) THE RIGHT—OF—WAY ON EAST ROPE MILL ROAD IS 5 FEET FROM THE EDGE OF ROAD, PER CHEROKEE COUNTY ROAD DEPARTMENT 4) REFERENCE) PLAT OF A PORTION OF RIGHT—OF—WAY AND TRACT MAP FOR:
LOUISVILLE—NASHVILLE RAILROAD COMPANY ATLANTA DIVISION, OLD LINE V46—SHEET 40."

5) REFERENCE: PLAT OF VOYLES ESTATE BY: A.W. ROBINSON, SURVEYOR. DATED: JAN. 5,

A.W. ROBINSON, SURVEYOR. DATED: JAN. 5, 1968.
6) REFERENCE: PLAT OF LOT #4 VOYLES SUBDIVISION, BY A.W. ROBINSON SURVEYOR. DATED: COT. 28, 1967. P.B. 4, PAGE 169. 7) BENCHMARK ELEVATION WAS TRANSFER FROM B.V. MON.. 028—18, DATED: JUNE 28, 1969. ELEVATION 1013.49 ROAD HAS BEEN ALTERED AND IS NO 8) CONGER CENTERED WITHIN R/W, R/W SHOWN IS PER REFERENCE MATERIAL.
9) REFERENCE PLAT OF A BOUNDARY SURVEY FOR GLEN NEDZA BY ADAMS—SIMS & ASSOC., INC. DATED SEPT. 8, 1999.

FROSION CONTROL NOTES:

) TOTAL DISTURBED AREA = 3.82 ACRE

1) IOIAL DISTURBED AREA = 3.82 ACRES
2) TOTAL DRAINED AREA = 3.82 ACRES
3) REQUIRED SEDIMENT STORAGE FOR THIS SITE IS 511.9 C.Y.
4) SUPPLIED STORAGE = 771 L.F. Sd1 x 0.1675 = 129.1 CY + Sd2
72' x 90' 2.5' = 600 CY TOTAL = 729.1 CY
5) GRASSING AND NATURAL VEGETATION WILL BE USED FOR WATER QUALITY ON THIS PROJECT.
PRE-DEVELOPED CN: 77 POST-DEVELOPED CN: 98
9. TOONICH CREEK IS AN IMPRIED STEPAM ED 700 E" FOUR ITEMS

PRE-DEVELOPED ON: 77 POST-DEVELOPED ON: 98 6) TOONIGH CREEK IS AN IMPAIRED STREAM FOR "BIO F" FOUR ITEM FROM APPENDIX "A" TO MITIGATE ARE ITEMS B.D.E & N. 7) AS INDICATED IN NOTE 6 THE USE OF FLOCCULANTS AND COAGULANTS SHALL BE IMPLAMENTED AS AN ADDITIONAL EROSION MEASURE.

NO BUFFER ENCROACHMENTS ARE PLANNED FOR THIS PROJECT. THIS PROJECT IS EXEMPT FROM THE VARIANCE REQUIREMENT. NO ENCROACHMENTS ARE PLANNED, THEREFORE NO VARIANCE


NO WETLANDS WERE OBSERVED.

IS REQUIRED.

EROSION CONTROL MEASURES FOR THIS PROJECT WILL INCLUDED INITIAL SEDIMENT STORAGE, PERIMETER CONTROL BMPS'S, INTITIAL STABILIZATION BMP'S, AND FINAL STABILIZATION BMP'S, AND UPON FINAL STABILIZATION, ALL EROSION CONTROL BMP'S SHALL BE REMOVED.

NO STATE WATERS WITHIN 200' OF DISTURBED AREA ARE SHOWN

For building materials, building products, construction wastes, trash, landscape materials, fertilizers, pesticides, herbicides, detergents, sanitary waste and other materials present on the site, provide cover (e.g. plastic sheeting, temporary roofs) to minimize the exposure of these products to precipitation and to stormwater, or a similarly effective means designed to minimize the discharge of pollutants from these areas. Minimization of exposure is not required in cases where exposure to precipitation and to stormwater will not result in a discharge of pollutants, or where exposure of a specific material or product poses little risk to stormwater contamination (such as final products and materials intended for outdoor use).



"ALL MATTERS OF TITLE ARE EXCEPTED"



EXISTING CONDITIONS PLAN FOR CHEROKEE 2

LOCATED IN LAND LOT(S): 592 DISTRICT - 15 . SECTION - 2 CHEROKEE COUNTY, GEORGIA

PREPARED: DEC. 27, 2019 SCALE: 1" = 50'


BY: WIKLE LAND SURVEYING, P.C. P.O. BOX 1164 CANTON, GEORGIA 30114 PHONE: (770) 479-8364



SOCIETY OF GEORGIA

N./F. LOLA V. STELL

(ZONED R-40)



CRAPHIC SCALE

NOTES:

1) THIS PLAT IS SUBJECT TO ALL EASEMENTS
AND RICHTS—OF—WAY PRIVATE AND PUBLIC.
2) UNDERGROUND UTILITIES AND/OR
STRUCTURES, IF ANY, MAY NOT BE SHOWN.
3) THE RIGHT—OF—WAY ON EAST ROPE MILL
ROAD IS 5 FEET FROM THE EDGE OF ROAD,
PER CHEROKEE COUNTY ROAD DEPARTMENT
4) REFERENCE) PLAT OF A PORTION OF
RICHT—OF—WAY AND TRACT MAP FOR:
LOUISVILLE—NASHVILLE RAILROAD COMPANY
ATLANTA DIVISION, "OLD LINE V46— SHEET
40." NO BUFFER ENCROACHMENTS ARE PLANNED FOR THIS PROJECT. THIS PROJECT IS EXEMPT FROM THE VARIANCE REQUIREMENT. NO ENCROACHMENTS ARE PLANNED, THEREFORE NO VARIANCE For building materials, building products, construction wastes, trash, landscape materials, fertilizers, pesticides, herbicides, detergents, sanitary waste and other 1) TOTAL DISTURBED AREA = 3.82 ACRE
2) TOTAL DRAINED AREA = 3.82 ACRES
3) REQUIRED SEDIMENT STORAGE FOR THIS SITE IS 511.9 C.Y.
4) SUPPLIED STORAGE = 771 LF. Sd1 x 0.1675 = 129.1 CY + Sd
72' x 90' 2.5' = 600 CY TOTAL = 729.1 CY materials present on the site, provide cover (e.g. plastic sheeting, temporary roofs) to minimize the exposure of these products to precipitation and to stormwater, or a similarly effective means designed to minimize the discharge of pollutants from these areas. Minimization of exposure is not required in cases where exposure to precipitation and to stormwater will not result in a discharge of pollutants, or where exposure of a specific material or product poses little risk to stormwater contamination (such as final broducts and materials intended for outdoor use). NO WETLANDS WERE OBSERVED. EROSION CONTROL MEASURES FOR THIS PROJECT WILL INCLUDED INITIAL SEDIMENT STORAGE, PERIMETER CONTROL BMPS'S, INTERMEDIATE DRAINAGE BMP'S, AND FINAL STABILIZATION BMP'S. AND UPON FINAL STABILIZATION, ALL EROSION CONTROL 5) GRASSING AND NATURAL VEGETATION WILL BE USED FOR WATER QUALITY ON THIS PROJECT. QUALITY ON THIS PROJECT.
PRE-DEVELOPED CN: 77 POST-DEVELOPED CN: 98
6) TOONIGH CREEK IS AN IMPAIRED STREAM FOR "BIO F" FOUR ITEM
FROM APPENDIX "A" TO MITIGATE ARE ITEMS B.D,E & N. contamination (such as final ts and materials intended for outdoor use). BMP'S SHALL BE REMOVED. 5) REFERENCE: PLAT OF VOYLES ESTATE BY: A.W. ROBINSON, SURVEYOR. DATED: JAN. 5, 7) AS INDICATED IN NOTE 6 THE USE OF FLOCCULANTS AND COAGULANTS SHALL BE IMPLAMENTED AS AN ADDITIONAL EROSION NO STATE WATERS WITHIN 200' OF DISTURBED AREA ARE SHOWN 1968.
6) REFERENCE: PLAT OF LOT #4 VOYLES SUBDIVISION, BY A.W. ROBINSON SURVEYOR. DATED: OCT. 28, 1967. P.B. 4, PAGE 169.
7) BENCHMARK ELEVATION WAS TRANSFER FROM B.V. MON. 028—18, DATED: JUNE 28, 1969. ELEVATION 1013.49
ROAD HAS BEEN ALTERED AND IS NO 8)
LONGER CENTERED WITHIN R/W, R/W SHOWN IS PER REFERENCE MATERIAL.
9) REFERENCE PLAT OF A BOUNDARY SURVEY FOR GLEN NEDZA BY ADAMS—SIMS & ASSOC., INC. DATED SEPT. 8, 1999. TRAVERSE TABLE COURSE BEARING DISTANCE 25°30'10"E 41.45° 52.97° L.L. 561 N 24°22'05"F N./F. <u>JEFFERY J. BURNETT</u> N 29°11'45"F 119,42 48.12' 49.73' 38.73' N 27°53'50"E 1 33°30'30"E N 40°00'20"E N 44°55'20"E N 42°26'35"E 61.18' 53.43' SAVE AREA L.L. 592 INFILTRATION TRENCH o' undisturibled zoning buffer LF.24"D.I.P PARKING REQUIREMENTS BUILDING "A" TOTAL AREA = 23,900 SQ FT OFFICE AREA 2000 SQ FT/285 = 7 SPACES FIELD ADJUST NEW WAREHOUSE 21,900 SQ FT/2,000 = 11 SPACES TOTAL SPACES REQUIRED = 18 TOTAL SPACES SUPPLIED = 42 INCLUDING 2 HANDICAP DRIVEWAY CONNECTIONS TO MATCH PLANNED NEW ROAD WAY BUILDING "B" TOTAL AREA = 23,900 SQ FT OFFICE AREA 2000 SQ FT/285 = 7 SPACES WAREHOUSE 21,900 SQ FT/2,000 = 11 SPACES TOTAL SPACES REQUIRED = 18 STREET ADDRESS 510 TOTAL SPACES SUPPLIED = 65 INCLUDING 4 HANDICAP POWER LINE TO BE REMOVED & EASEMENT ABANDONED N./F. ALENE CALLAHAN (ZONED R-40) - R30.0000° EXAMPLE DUMPSTER ENCLOSED SEE SHEET 9 FOR DETAILS PUNE TRANSFORMER ZONE D SEE SHEET 21 FOR NOTES DUMPSTER PADS TO BE ENCLOSED BY 6' TALL SCREEN SUCH AS WOOD FENCE OR WALL (SEE EXAMPLE) TREE SAVE POWER TRANSFORMER TO BE PLACED NO CLOSER THAN 10' FROM BUILDING, OVERHANGS, CANOPIES, EXTERIOR WALLS. BALCONIES. EXTERIOR STAIRS AND/OR WALKWAYS
CONNECTED TO BUILDING N./F. LOLA V. STELL (ZONED R-40) STREET AS WELL AS ANY WINDOW ADDRESS 500 i./f. <u>Nellie mae temple</u> (ZONED R-40) CHEROKEE 2 LOCATED IN LAND LOT(S): 592 DISTRIBUTE-PLAN, ISOSTION - 2 CHEROKEE COUNTY, GEORGIA PREPARED: DEC. 27, 2019 SCALE: 1" = 50' 24" DIA PIPE St <u>DIMENSIONS:</u> Y: WIKLE LAND SURVEYING, P.C. P.O. BOX 1164 CANTON, GEORGIA 30114 PHONE: (770) 479-8364 UPSTREAM-WIDTH: 6.<u>0'</u> CHEROKEE PMC LLC DOWNSTREAM (ZONED: LI) BENCH MARK ELEV. 1019.97' TOP OF I.P.F. (AXLE) AVG. STONE DIA (d50): 12" LENGTH: 12.0' APRON THICKNESS: 1.0' SOCIETY OF GEORGIA N./F. <u>W.B. ANDERSON</u> (ZONED R-40) AREA = 4.39 ACRESSHEET 3 OF 23 SHEETS

"ALL MATTERS OF TITLE ARE EXCEPTED"

FIELD BOOK 52 ,PAGE 41 ,FILE R 1061. I FGFND I.P.S. — IRON PIN SET (#5 R.)
I.P.F. — IRON PIN FOUND
I.L.L. — LAND LOT LINE
IR/W — RIGHT OF WAY - PROPERTY LINE - CENTER LINE - REINFORCING BAR P.P. - POWER &(OR) PHONE POLE N./F. - NOW OR FORMERLY LINE
12) B.L. - BUILDING LINE
13) D.E. - DRAINAGE EASEMENT
14) S.S.E. - SANITARY SEWER
EASEMENT
16) P.A.M.E. - POND ACCESS & MANAGEMENT EASEMENT
17) — TSW— - TREE SAVE FENCE THE FIELD DATA UPON WHICH THIS PLAT IS BASED HAS A CLOSURE PRECISION OF ONE FOOT IN 10,000+FEET AND AN ANGULAR ERROR OF 02'PER ANGLE POINT AND WAS ADJUSTED USING THE COMPASS RULE. THIS PLAT HAS BEEN CALCULATED FOR CLOSURE AND FOUND TO BE ACCURATE WITHIN ONE FOOT IN 100,000+ FEET. EQUIPMENT USED FOR MEASUREMENTS: TOPCON GTS - 303, TOTAL STATION

https://tinyurl.com/tjqpvso

The entire stormwater management system, including all conveyance, storage, treatment, flowrates, etc. will need to be analyzed by a Georgia registered engineer, using "as-built" data

provided by a Georgia registered land surveyor prior to site release/certificate of occupancy. Contact the Engineering Department

A Stormwater Maintenance Agreement is required for this project prior to the final plat site release/certificate of occupancy. A draft copy of the required agreement can be downloaded from A draft copy of the required agreement can be downloaded from the Cherokee County Stormwater Management website under The forms and documents tab

The Stormwater Maintenance Agreement should be submitted via e-mail or on Citiview for preliminary review and approval. Please note that Exhibits A, B, C, and D must be included and must be customized for the project under review. After preliminary approval, the original omplete document should be submitted to the Engineering

Department for signature by the County Engineer and notarized. The agreement must then be picked up by the applicant and recorded with the Cherokee County Clerk of Court (Deeds and Records Department). Deeds and records only accepts original documents with the notary seal, and they must be 8.5x11 or 8.5x14. The recorded document must be returned to Cherokee County Engineering Department prior to issuance of a final plat or site release/certificate of occupancy.

It is the policy of Cherokee County that drainage easements are dedicated to the public use and are not accepted by Cherokee County for County maintenance and are not considered County property. It is

right-of-way per policy adopted January 14, 1997.

Cherokee County policy that no County forces or equipment shall be used to perform construction to any drainage easement within Cherokee County, unless said easement lies within Cherokee County right-of-way and/or said work is necessary to protect County

Cherokee County shall not be responsible for maintenance of any pipes,

ditches, detention ponds, water quality structures, or other structures within any drainage easement and/or outside the County right-of-way.

at 678-493-6074 or blmorgan@cherokeega.com for additional

NOTES:

1) THIS PLAT IS SUBJECT TO ALL EASEMENTS AND RIGHTS—OF—WAY PRIVATE AND PUBLIC.

2) UNDERGROUND UTILITIES AND/OR STRUCTURES, IF ANY, MAY NOT BE SHOWN.

3) THE RIGHT—OF—WAY ON EAST ROPE MILL ROAD IS 5 FEET FROM THE EDGE OF ROAD, PER CHEROKEE COUNTY ROAD DEPARTMENT 4) REFERENCE) PLAT OF A PORTION OF RIGHT—OF—WAY AND TRACT MAP FOR:

LOUISVILLE—NASHVILLE RAILROAD COMPANY ATLANTA DIVISION, "OLD TIEN V46— SHEET 40." 5) REFERENCE: PLAT OF VOYLES ESTATE BY: A.W. ROBINSON, SURVEYOR. DATED: JAN. 5, 1988. 6) REFERENCE: PLAT OF LOT #4 VOYLES SUBDINSION, BY A.W. ROBINSON SURVEYOR. DATED: OCT. 28, 1967. P.B. 4, PAGE 169. 7) BENCHMARK ELEVATION WAS TRANSFER FROM B.V. MON. 028-18, DATED: JUNE 28, 1968. ELEVATION 1013.49
ROAD HAS BEEN ALTERED AND IS NO 8) LONGER CENTERED WITHIN R/W, R/W SHOWN IS PER REFERENCE WATERIAL.

9) REFERENCE PLAT OF A BOUNDARY SURVEY FOR GLEN NEDZA BY ADAMS—SIMS & ASSOC., INC. DATED SEPT. 8, 1999.

5) GRASSING AND NATURAL VEGETATION WILL BE USED FOR WATER QUALITY ON THIS PROJECT. PRE—DEVELOPED CN: 77 POST—DEVELOPED CN: 98
6) TOONIGH CREEK IS AN IMPAIRED STREAM FOR "BIO F" FOUR ITEMS FROM APPENDIX "A" TO MITIGATE ARE ITEMS B.D.E & N.
7) AS INDICATED IN NOTE 6 THE USE OF FLOCCULANTS AND
COACULANTS SHALL BE IMPLAMENTED AS AN ADDITIONAL EROSION
MEASURE.

1) TOTAL DISTURBED AREA = 3.82 ACRE
2) TOTAL DRAINED AREA = 3.82 ACRES
3) REQUIRED SEDIMENT STORAGE FOR THIS SITE IS 511.9 C.Y.
4) SUPPLIED STORAGE = 771 L.F. Sd1 x 0.1675 = 129.1 CY + 72' x 90' 2.5' = 600 CY TOTAL = 729.1 CY

NO BUFFER ENCROACHMENTS ARE PLANNED FOR THIS PROJECT. THIS PROJECT IS EXEMPT FROM THE VARIANCE REQUIREMENT. NO ENCROACHMENTS ARE PLANNED, THEREFORE NO VARIANCE

NO WETLANDS WERE OBSERVED.

EROSION CONTROL MEASURES FOR THIS PROJECT WILL INCLUDED INITIAL SEDIMENT STORAGE, PERIMETER CONTROL BMPS'S, INTERMEDIATE DRAINAGE BMP'S, AND FINAL STABILIZATION BMP'S, AND UPON FINAL STABILIZATION, ALL EROSION CONTROL BMP'S SHALL BE REMOVED.

NO STATE WATERS WITHIN 200' OF DISTURBED AREA ARE SHOWN

For building materials, bui materials, fertilizers, pesti products, construction wastes, trash, landscape herbicides, detergents, sanitary waste and other materials, fertilizers, pesticides, herbicides, detergents, sanitary waste and other materials present on the site, provide cover (e.g. plastic sheeting, temporary roofs) to minimize the exposure of these products to precipitation and to stormwater, or a similarly effective means designed to minimize the discharge of pollutants from these areas. Minimization of exposure is not required in cases where exposure to precipitation and to stormwater will not result in a discharge of pollutants, or where exposure of a specific material or product poses little risk to stormwater contamination (such as find products and materials intended for outdoor use).



TRAVERSE TABLE BEARING DISTANCE N 21°20'55"E N 25°30'10"E N 24°22'05"E 52 97 N 29*11'45"E N 29*56'35"E 119.42 N 27°53'50"E 48.12 49.73' 38.73' N 33°30'30"E N 40°00'20"E N 44°55'20"E 10 11 N 42°26'35"F 53.43 N 40°49'55"E 69.65

BENCH MARK

INFILTRATION TRENCH 3' TALL FOREBAY °µ 90°00'000"E 176.70' ACTIVE TREE SAVE FENCE FORFRAY _ENHANCED SWALE DOWNSTREAM OF FOREBAY ALL WEIRS AND ORIFICES TO HAVE TRASH RACKS AND/OR DEBRIS CAGES SEE SHEET 11 FOR POND CROSS-SECTION & OUTLET CONTROL STRUCTURE DETAIL PROPOSED 23900 SQFI BUILDING F.F. ELEV ALL DISTURBED AREA AND 45,000 SQFT OF PARKING IMPERVIOUS AREAS TO DRAIN TO POND POWER TRANSFORMER 35,700 SQFT OF PARKING PROPOSED 23900 SOFT BUILDING F.F. ELEV 1008.5 STREET ADDRESS 500 DPSTR. ELEV 1008.0 EXIST. PIV W 6703'00"W 327.82' ACTIVE TREE SAVE FENCE ACTIVE TREE SAVE FENCE 24" DIA PIPE St DIMENSIONS: UPSTREAM-**DOWNSTREAM** WIDTH: 6.0' AVG. STONE DIA (d50): 12" LENGTH: 12.0' APRON THICKNESS: 1.0'

AREA = 4.39 ACRES

"ALL MATTERS OF TITLE ARE EXCEPTED"

5 TALL FENCE AROUND ENTIRE PERIMETER OF POND ALSO TO SERVE _

AS FALL PROTECTION

GRADING PLAN FOR:

CHEROKEE 2

LOCATED IN LAND LOT(S): 592 DISTRICT - 15 , SECTION - 2 CHEROKEE COUNTY, GEORGIA


PREPARED: DEC. 27, 2019 SCALE: 1" = 50'

BY: WIKLE LAND SURVEYING, P.C. P.O. BOX 1164 CANTON, GEORGIA 30114 PHONE: (770) 479-8364

479-8364 SURVEYING AND MAPPING

SOCIETY OF GEORGIA

SHEET 4 OF 23 SHEETS



OB NO.

CHECKED

DATE

10/15/21 COMMENTS

MILL ROAD, CANTON, GA 30115

TREE REMOVAL &

10/4/21


21021lw1

21021

1"=50"

5 OF 20

REPLACEMENT



NOTES:

1) THIS PLAT IS SUBJECT TO ALL EASEMENTS AND RIGHTS—OF—WAY PRIVATE AND PUBLIC.

2) UNDERGROUND UTILITIES AND/OR STRUCTURES, IF ANY, MAY NOT BE SHOWN.

3) THE RIGHT—OF—WAY ON EAST ROPE MILL ROAD IS 5 FEET FROM THE EDGE OF ROAD, PER CHEROKEE COUNTY ROAD DEPARTMENT

4) REFERENCE) PLAT OF A PORTION OF RIGHT—OF—WAY AND TRACT MAP FOR:

COUNSYILLE—NASHVILLE RAILROAD COMPANY ATLANTA DIVISION, "OLD LINE V46— SHEET 40." FIELD BOOK 52 ,PAGE 41 ,FILE R 1061.

I.P.S. — IRON PIN SET (#5 R.) I.P.F. — IRON PIN FOUND I.L.L. — LAND LOT LINE IR/W — RIGHT OF WAY

OVERHEAD UTILITY

16) P.A.M.E. - POND ACCESS & IANAGEMENT EASEMENT 7) — TSW— - TREE SAVE FENCE

THIS PLAT HAS BEEN CALCULATED FOR CLOSURE AND FOUND TO BE ACCURATE WITHIN ONE FOOT IN 100,000+ FEET.

/ W - ...

- PROPERTY LINE

- CENTER LINE

R. - REINFORCING BAR

P.P. - POWER & (OR) PHONE POLE

N./F. - NOW OR FORMERLY

- FENCE (APPROX.

THE FIELD DATA UPON WHICH THIS PLAT IS BASED HAS A CLOSURE PRECISION OF ONE FOOT IN 10,000+FEET AND AN ANGULAR ERROR OF 02*PER ANGLE POINT AND WAS ADJUSTED HISTOR THE COMPASS BILLS

EQUIPMENT USED FOR MEASUREMENTS: TOPCON GTS - 303, TOTAL STATION

PROJECT NAME AND LOCATION GLEN NEDZA 500 E. ROPE MILL ROAD CANTON, GEORGIA 30115 OWNER: GLEN NEDZA 500 E. ROPE MILL ROAD CANTON, GEORGIA 30115


SCALE - FFFT

DESCRIPTION:

PRE DEVELOPMENT SITE CHARACTERISTICS: THE SITE IS LOCATED IN LAND LOT 592 OF THE 15TH DISTRICT, 2ND SECTION IN CHEROKEE COUNTY, GEORGIA. THE SITE IS AN UN—DEVELOPED TRACT OF RAW LAND AND IS BORDERED ON THE SOUTH AND NORTH BY OTHER UN—DEVELOPED PROPERTY. IT IS BORDERED ON THE WEST BY E. ROPE MILL ROAD, IT IS BORDERED ON THE EAST BY RAILROAD TRACT. THE HIGH POINT OF THIS PROPERTY IS TO WEST CENTER OF THE PROPERTY AT APPROXIMATELY ELEVATION 1012. RUNOFF FLOWS IN A XXX DIRECTION EVENTUALLY REACHING TOONIGH CREEK. THE LOWEST POINT OF THE PROPERTY IS APPROXIMATELY ELEVATION 1012. RUNOFF FLOWS IN A XXX DIRECTION EVENTUALLY REACHING TOONIGH CREEK. THE LOWEST POINT OF THE PROPERTY IS APPROXIMATELY ELEVATION 980 AT THE NORTHEASTERN SIDE OF THE PROPERTY. THE SITE HAS NO DELINEATED WETLANDS. REVIEW OF FEMA FIRM MAPS INDICATE THAT THE PROPERTY DOES NOT LIE IN ANY FLOOD HAZARD AREA, AS SHOWN ON COMMUNITY PANEL 1305FOC244E FOR CHEROKEE COUNTY, GEORGIA, DATED JUNE 07, 2019. SOIL CLASSIFICATIONS ON THE SITE ARE AS SHOWN.

SOIL DISTURBING ACTIVITES WILL INCLUDE:

CLEARING AND GRUBBING, EXCAVATION FOR FOUNDATIONS, DRIVEWAYS, SEPTIC SYSTEMS, DETENTION PONDS AND YARD PREPERATION AND SEEDING. INITIAL CONTROLS WILL BE THE PERIMETER CONTOL WILL SOLD IN STEMPS IN TERMEDIATE CONTROL WILL CONTINUE WITH SD1-NS, THE FINAL PHASE WILL BE USING PERMINATE VEGITATION AND REMOVAL OF ALL OTHER EROSOPN



EROSION CONTROL NOTES:

5) REFERENCE: PLAT OF VOYLES ESTATE BY: A.W. ROBINSON, SURVEYOR. DATED: JAN. 5,

A.W. ROBINSON, SURVEYOR. DATED: JAN. 5, 1968.
6) REFERENCE: PLAT OF LOT \$\frac{4}\$ VOYLES
SUBDIMSION, BY A.W. ROBINSON SURVEYOR.
DATED: OCT. 28, 1967. P.B. 4, PAGE 169.
7) BENCHMARK ELEVATION WAS TRANSFER
FROM B.V. MON. 028-18, DATED: JUNE 28, 1969. ELEVATION 1013.49
ROAD HAS BEEN ALTERED AND IS NO 8)
LONGER CENTERED WITHIN R/W, R/W SHOWN IS PER REFERENCE MATERIAL.
9) REFERENCE PLAT OF A BOUNDARY SURVEY
FOR GLEN NEDZA BY ADAMS—SIMS & ASSOC.,
INC. DATED SEPT. 8, 1999.

TOTAL DISTURBED AREA = 3.82 ACRE

TRAVERSE TABLE

BEARING

21°20'55"E

24°22'05"E

N 23°48'00"E N 29°11'45"E

29°56'35"E 27°53'50"E

33°30'30"E

N 40°00'20"E

N 44°55'20"E N 42°26'35"E

Du

Ds1

Ds2

Ds3

Ds4

LOLA V. STELL

(ZONED R-40)

) TOTAL DRAINED AREA = 3.82 ACRES 3) REQUIRED SEDIMENT STORAGE FOR THIS SITE IS 511.9 C.Y.
4) SUPPLIED STORAGE = 771 L.F. Sd1 x 0.1675 = 129.1 CY + Sd

 $72' \times 90' \ 2.5' = 600 \ CY \ TOTAL = 729.1 \ CY$ 72 x 90 2.5 = 600 CF IONAL = 729.1 CF 5) GRASSING AND NATURAL VEGETATION WILL BE USED FOR WATER QUALITY ON THIS PROJECT. PRE-DEVELOPED CN: 77 POST-DEVELOPED CN: 98

6) TOONIGH CREEK IS AN IMPAIRED STREAM FOR "BIO F" FOUR ITEMS FROM APPENDIX "A" TO MITIGATE ARE ITEMS B.D.E & N.
7) AS INDICATED IN NOTE 6 THE USE OF FLOCCULANTS AND
COAGULANTS SHALL BE IMPLAMENTED AS AN ADDITIONAL EROSION

DISTANCE

15.74

52.97

119.42

55.12' 48.12'

49.73' 38.73'

61.18' 53.43'

LIMITS OF DISTURBANCE

ALENE CALLAHAN (ZONED R-40)

34.1473 84.5089

CO

NO BUFFER ENCROACHMENTS ARE PLANNED FOR THIS PROJECT. THIS PROJECT IS EXEMPT FROM THE VARIANCE REQUIREMENT. NO ENCROACHMENTS ARE PLANNED, THEREFORE NO VARIANCE IS REQUIRED.

MiC2

PROPOSED 23900 SOFT BUILDING

F.F. ELEV

1008.5

ADDRESS

500

327.82

67:03:00 W

CHEROKEE PMC LLC (ZONED: LI)

STREET

NO WETLANDS WERE OBSERVED.

For building materials, building products, construction wastes, trash, landscape materials, fertilizers, pesticides, herbicides, detergents, sanitary waste and other materials present on the site, provide cover (e.g. plastic sheeting, temporary roofs) to minimize the exposure of these products to precipitation and to stormwater, or a similarly effective means designed to minimize the discharge of pollutants from these areas. Minimization of exposure is not required in cases where exposure to precipitation and to stormwater will not result in a discharge of pollutants, or where exposure of a specific material or product poses little risk to stormwater

EROSION CONTROL MEASURES FOR THIS PROJECT WILL INCLUDE INITIAL SEDIMENT STORAGE, PERIMETER CONTROL BMPS'S, ONTERMEDIATE DRAINAGE BMP'S, AND FINAL STABILIZATION ALL EROSIONSCONTROLFENCE—AROUND—ENTIRE PERIMETER OF STABLE AND TO SERVE contamination (such as final products and materials intended for outdoor use). NO STATE WATERS WITHIN 200' OF DISTURBED AREA RONG HAND TO SERVE FOR RETAINING WALL SkL.L. 561 JEFFERY J. BURNETT Ss (WM8) (ZONED R-40) CO 90°00'00"E 176.70' _Stc)IVE TREE SAVE FENCE SAVE AREA /_{L.L.}\ \592 Sd3FLOC LOGS TO BE PLACED IN SWALES AND FLUMES DURING 25 <u>LF.24</u> D.I.P CONSTRUCTION 2'V×1'D FLUME Rp Ss SAMPLING 100 LOCATION Sd2 7 PROPOSED 23900 SQFT BUILDING CURB TO F.F. ELEV 996.5' STREET / Di ADDRESS 510

45,500 SQFT OF PARKING

LOT

400

ACTIVE TREE SAVE FENCE

N./F.

RAILROAD

~

S.

Zitterw.

ELEY

35,700 SQFT OF

PARKING LOT

DPSTR. ELEV 1008.0

AREA = 4.39 ACRES

"ALL MATTERS OF TITLE ARE EXCEPTED"

"I CERTIFY THAT THE PERMITTEE'S EROSION,
SEDIMENTATION AND POLLUTION CONTROL PLAN PROVIDES FOR AN APPROPRIATE AND COMPREHENSIVE SYSTEM OF BEST MANAGEMENT PRACTICES REQUIRED BY THE GEORGIA WATER QUALITY CONTROL ACT AND THE DOCUMENT "MANUAL FOR EROSION AND SEDIMENTATION CONTROL IN GEORGIA" (MANUAL) PUBLISHED BY THE STATE SOIL AND WATER CONSERVATION COMMISSION AS OF JANUARY 1 OF THE YEAR IN WHICH THE LAND DISTURBING ACTIVITY WAS PERMITTED," PROVIDES FOR THE SAMPLING OF THE RECEIVING WATERS OR THE SAMPLING OF THE STORM WATER OUTFALLS AND THAT THE DESIGNED SYSTEM OF BEST MANAGEMENT PRACTICES AND SAMPLING METHODS IS EXPECTED TO MEET THE REQUIREMENTS CONTAINED IN THE GENERAL NPDES PERMIT NO. GAR 100003."

FURTHER CERTIFY UNDER PENALTY OF LAW THAT HIS PLAN WAS PREPARED AFTER A SITE VISIT TO THE LOCATIONS DESCRIBED HERE IN BY MYSELF OR MY AUTHORIZED AGENT, UNDER MY DIRECT

MJB - MADISON FINE SANDY LOAM, 2-6% SLOPE ThE2 - TALLAPOOSA GRAVELLY SANDY CLAY LOA 10-25% SLOPES, ERODED MiC2 - MADISON GRAVELLY SANDY CLAY LOAM. 2-10% SLOPES, ERODED

DOWNSTREAM

24" DIA PIPE St <u>DIMENSIONS:</u>

-LIMITS OF DISTURBANCE

Sd1-NS

Du

Ds1

Ds2

Ds3

LIPSTREAM-

WIDTH: 6.0'

Ss

NELLIE MAE TEMPLE

(ZONED R-40)

PHASE II EROSION PLAN FOR:

CHEROKEE 2


LOCATED IN LAND LOT(S): 592 DISTRICT - 15 , SECTION - 2 CHEROKEE COUNTY, GEORGIA

PREPARED: DEC. 27, 2019 SCALE: 1" = 50'

BY: WIKLE LAND SURVEYING, P.C. P.O. BOX 1164 CANTON, GEORGIA 30114 PHONE: (770) 479-8364



AVG. STONE DIA (d50): 12" LENGTH: 12.0' APRON THICKNESS: 1.0'



BENCH MARK ELEV. 1019.97' TOP OF I.P.F. (AXLE)

SHEET 7 OF 23 SHEETS

NOTES:

1) THIS PLAT IS SUBJECT TO ALL EASEMENTS AND RIGHTS—OF—WAY PRIVATE AND PUBLIC.

2) UNDERGROUND UTILITIES AND/OR STRUCTURES, IF ANY, MAY NOT BE SHOWN.

3) THE RIGHT—OF—WAY ON EAST ROPE MILL ROAD IS 5 FEET FROM THE EDGE OF ROAD, PER CHEROKEE COUNTY ROAD DEPARTMENT

4) REFERENCE) PLAT OF A PORTION OF RIGHT—OF—WAY AND TRACT MAP FOR:
LOUISVILLE—NASHVILLE RAILROAD COMPANY ATLANTA DIVISION, "OLD LINE V46— SHEET

40." NO BUFFER ENCROACHMENTS ARE PLANNED FOR THIS PROJECT. THIS PROJECT IS EXEMPT FROM THE VARIANCE REQUIREMENT. NO ENCROCACHMENTS ARE PLANNED, THEREFORE NO VARIANCE IS DECURED. EROSION CONTROL NOTES: For building materials, building products, construction wastes, trash, landscape materials, fertilizers, pesticides, herbicides, detergents, sanitary waste and other FIELD BOOK <u>52</u> ,PAGE <u>41 ,</u>FILE <u>R 1061.</u>) Total disturbed area = 3.82 acre) Total drained area = 3.82 acres) Required sediment storage for this site is 511.9 c.y. materials present on the site, provide cover (e.g. plastic sheeting, temporary roofs) to minimize the exposure of these products to precipitation and to stormwater, or a similarly effective means designed to minimize the discharge of pollutants from these LEGEND . — IRON PIN SET (#5 R.) . — IRON PIN FOUND . — LAND LOT LINE — RIGHT OF WAY PROPERTY LINE NO WETLANDS WERE OBSERVED. SUPPLIED STORAGE = 771 L.F. Sd1 x 0.1675 = 129.1 CY + Sd arreas. Minimization of exposure is not required in cases where exposure to precipitation and to stormwater will not result in a discharge of pollutants, or where exposure of a specific material or product poses little risk to stormwater EROSION CONTROL MEASURES FOR THIS PROJECT WILL INCLUDED INITIAL SEDIMENT STORAGE, PERIMETER CONTROL BMPS'S, INTERMEDIATE DRAINAGE BMPS'S, AND FINAL STABILIZATION BMP'S, AND UPON FINAL STABILIZATION, ALL EROSTOTACON FENCE 72' x 90' 2.5' = 600 CY TOTAL = 729.1 CY 5) GRASSING AND NATURAL VECETATION WILL BE USED FOR WATER QUALITY ON THIS PROJECT.
PRE—DEVELOPED CN: 77 POST—DEVELOPED CN: 98
6) TOONIGH CREEK IS AN IMPAIRED STREAM FOR "BIO F" FOUR ITEMS contamination (such as final products and materials intended for outdoor use) CENTER LINE - REINFORCING BAR BMP'S SHALL BE REMOVED.

BMP'S SHALL BE REMOVED.

ENTIRE PERIMETER OF

NO STATE WATERS WITHIN 200' OF DISTURBED AROUND ALSO WO SERVE

AREA FALL PROTECTION

FOR RETAINING WALL FROM APPENDIX "A" TO MITIGATE ARE ITEMS B.D.E & N.
7) AS INDICATED IN NOTE 6 THE USE OF FLOCCULANTS AND
COAGULANTS SHALL BE IMPLAMENTED AS AN ADDITIONAL EROSION
MEASURE. P.P. - POWER &(OR) PHONE POLE N./F. - NOW OR FORMERLY J.) REFERENCE: PLAT OF VOYLES ESTATE BY: W. ROBINSON, SURVEYOR. DATED: JAN. 5, - FENCE (APPROX. 1988.
6) REFERENCE: PLAT OF LOT #4 VOYLES SUBDIVISION, BY A.W. ROBINSON SURVEYOR. DATED: OCT. 28, 1967. P.B. 4, PAGE 169.
7) BENCHMARK ELEVATION WAS TRANSFER FROM B.W. MON.. 028–18, DATED: JUNE 28, 1969. ELEVATION 1013.49
ROAD HAS BEEN ALTERED AND IS NO 8)
LONGER CENTERED WITHIN R/W, R/W SHOWN IS PER REFERENCE MATERIAL.
9) REFERENCE PLAT OF A BOUNDARY SURVEY FOR GLEN NEDZA BY ADAMS—SIMS & ASSOC., INC. DATED SEPT. 8, 1999. - OVERHEAD UTILITY LINE.
12) B.L. – BUILDING LINE.
13) D.E. – DRAINAGE EASEMENT.
14) S.S.E. – SANITARY SEWER.
EASEMENT.
16) P.A.M.E. – POND ACCESS & L.L. 561 TRAVERSE TABLE JEFFERY J. BURNETT Ss (ZONED R-40) COURSE DISTANCE MANAGEMENT EASEMENT 1000 17) - TSW- - TREE SAVE FENCE 21°20'55"E 15.74 90°00**′0**0″E 176.70 41.45 I CERTIFY THAT THE PERMITTEE'S EROSION,
SEDIMENTATION AND POLLUTION CONTROL PLAN PROVIDES 3 THE FIELD DATA UPON WHICH THIS PLAT IS BASED HAS A CLOSURE PRECISION OF ONE FOOT IN 10,000+FEET AND AN ANGULAR ERROR OF 0.2" PER ANGLE POINT AND WAS ADJUSTED USING THE COMPASS RULE. 52.97 24°22'05"F Stojive tree save fence 55.47' 119.42' FOR AN APPROPRIATE AND COMPREHENSIVE SYSTEM OF BEST MANAGEMENT PRACTICES REQUIRED BY THE 29°11'45"E REA SAVE AREA L.L. 592 29°56'35"E GEORGIA WATER QUALITY CONTROL ACT AND THE DOCUMENT "MANUAL FOR EROSION AND SEDIMENTATION 48 12 N 33°30'30"E N 40°00'20"E 49.73' 38.73' CONTROL IN GEORGIA" (MANUAL) PUBLISHED BY THE STATE SOIL AND WATER CONSERVATION COMMISSION AS THIS PLAT HAS BEEN CALCULATED FOR CLOSURE AND FOUND TO BE ACCURATE WITHIN ONE FOOT IN 100,000+ FEET. FLOC LOGS TO BE 61.18' 53.43' 44°55'20"E OF JANUARY 1 OF THE YEAR IN WHICH THE LAND PLACED IN SWALES OF JANOART OF THE LEAR IN WHICH THE JAND
DISTURBING ACTIVITY WAS PERMITTED," PROVIDES FOR
THE SAMPLING OF THE RECEIVING WATERS OR THE
SAMPLING OF THE STORM WATER OUTFALLS AND THAT
THE DESIGNED SYSTEM OF BEST MANAGEMENT PRACTICES
AND SAMPLING METHODS IS EXPECTED TO MEET THE
REQUIREMENTS CONTAINED IN THE GENERAL NPDES 42°26'35"E 40°49'55"E AND FLUMES DURING EQUIPMENT USED FOR MEASUREMENTS TOPCON GTS - 303, TOTAL STATION 25 <u>TF.24</u> D.I.P CONSTRUCTION 2'\v\z1'1) FLUME PROJECT NAME AND LOCATION 404 \sqrt{Rp} GLEN NEDZA 500 E. ROPE MILL ROAD Ss SAMPLING PERMIT NO. GAR 100003." LOCATION CANTON, GEORGIA 30115 457 ROPE WILL I FURTHER CERTIFY UNDER PENALTY OF LAW THAT THIS PLAN WAS PREPARED AFTER A SITE VISIT TO OWNER: GLEN NEDZA 500 E. ROPE MILL ROAD THE LOCATIONS DESCRIBED HERE IN BY MYSELF OR 481 Sd2 CANTON, GEORGIA 30115 MY AUTHORIZED AGENT, UNDER MY DIRECT SUPERVISION. PROPOSED 23900 SQFT DESCRIPTION: DESCRIPTION:

PRE DEVELOPMENT SITE CHARACTERISTICS: THE SITE IS LOCATED IN LAND LOT 592 OF THE 15TH DISTRICT, 2ND SECTION IN CHEROKEE COUNTY, GEORGIA. THE SITE IS AN UN—DEVELOPED TRACT OF RAW LAND AND IS BORDERED ON THE SOUTH AND NORTH BY OTHER UN—DEVELOPED PROPERTY. IT IS BORDERED ON THE WEST BY E. ROPE MILL ROAD, IT IS BORDERED ON THE EAST BY RAILROAD TRACT. THE HIGH POINT OF THIS PROPERTY IS TO WEST CENTER OF THE PROPERTY AT APPROXIMATELY ELEVATION 1012. RUNOFF FLOWS IN A XXX DIRECTION EVENTUALLY REACHING TOONIGH CREEK. THE LOWEST POINT OF THE PROPERTY IS APPROXIMATELY ELEVATION 980 AT THE NORTHEASTERN SIDE OF THE PROPERTY. THE SITE HAS NO DELINEATED WETLANDS. REVIEW OF FEMA FIRM MAPS INDICATE THAT THE PROPERTY DOES NOT LIE IN ANY FLOOD HAZARD AREA, AS SHOWN ON COMMUNITY PANEL 1305700244E FOR CHEROKEE COUNTY, GEORGIA, DATED JUNE 07, 2019. SOIL CLASSIFICATIONS ON THE SITE ARE AS SHOWN. BUILDING F.F. ELEV 996.5' STREET ADDRESS 510 LIMITS OF DISTURBANCE 45,500 SQFT OF PARKING -LIMITS OF DISTURBANCE ALENE CALLAHAN (ZONED R-40) Du **3**4.1473 SOIL DISTURBING ACTIVITES WILL INCLUDE: -84.5089 Ds1 MjB - MADISON FINE SANDY LOAM, 2-6% SLOPES ELEV CLEARING AND GRUBBING, EXCAVATION FOR FOUNDATIONS, DRIVEWAYS, SEPTIC SYSTEMS, DETENTION PONDS AND YARD PREPERATION AND SEEDING. INITIAL CONTROLS WILL BE THE PERIMETER CONTOL WILL SOUTHOL WILL CONTINUE WITH SD1-NS, THE FINAL PHASE WILL BE USING 997.0 ThE2 - TALLAPOOSA GRAVELLY SANDY CLAY LOAM 0-25% SLOPES, ERODED <u>MiC2 — MADISON GRAVELLY SANDY CLAY LOAM,</u> Ds2MiC2 2-10% SLOPES, ERODED PERMINATE VEGITATION AND REMOVAL OF ALL OTHER EROSOPN CONTROL FEATURES. Ss Ds3 $\mathbf{D}\mathbf{u}$ 35,700 SQFT OF WEEKLY CONSTRUCTION ACTIVITY SCHEDULE TREE SAVE PARKING 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 ACTIVITY Ds4SEDIMENT CONTROLS Ds1TREE PORTECTION PROPOSED NPDES BMP'S INSPECTIONS 400 CLEARING AND GRAD BUILDING Ds2 F.F. ELEV LOLA V. STELL HOUSE CONTRUCTION 1008.5 RAILROAD (ZONED R-40) STREET GRASS (TEMP.) (PERM ADDRESS PHASE III EROSION PLAN FOR: NELLIE MAE TEMPLE Ds3500 (ZONED R-40) UTILITY INSTALLATION DPSTR CHEROKEE 2 ELEV 1008.0 MAINTAIN EROSION CONTROL Ds4 LOCATED IN LAND LOT(S): 592 DRIVEWAY PAVING ~ 67-03'90'W DISTRICT - 15 , SECTION - 2 FINAL LANDSCAPIN g CHEROKEE COUNTY, GEORGIA 327.82 10 CLEAN UP PREPARED: DEC. 27, 2019 SCALE: 1" = 50' 24" DIA PIPE St <u>DIMENSIONS:</u> PLAN APPROVAL DATE WILL BE CONSIDERED THE START OF THIS SCHEDULE ACTIVE TREE SAVE FENCE BY: WIKLE LAND SURVEYING, P.C. P.O. BOX 1164 UPSTREAM-CANTON, GEORGIA 30114 PHONE: (770) 479-8364 WDTH: 6.0' DOWNSTREAM 479-8364 AVG. STONE DIA (d50): 12" SURVEYING AND MAPPIN LENGTH: 12.0' APRON THICKNESS: 1.0' SOCIETY OF GEORGIA CHEROKEE PMC LLC (ZONED: LI) AREA = 4.39 ACRES ELEV. 1019.97 TOP OF I.P.F. "ALL MATTERS OF TITLE ARE EXCEPTED" (AXLE) N./F.

OTHER CONTROLS SPILL CONTROL PRACTICES SEEDING SCHEDULE SITE MAPS:

* SEE ATTACHED PLAN FOR ,
AREAS OF SOILS, DISTURBANCE, LOCATION OF SURFACE WATERS, WETLANDS,
PROTECTED AREAS, MAJOR STRUCTURAL AND NONSTRUCTURAL CONTROLS
AND STORM WATER DISCHARCE POINTS. IN ADDITION TO THE GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS SECTIONS OF THIS PLAN, THE FOLLOWING PRACTICES WILL BE FOLLOWED FOR SPILL PREVENTION AND WASTE DISPOSAL DATES SPECIES APPLICATION RATES CODE PRACTICE DETAIL 10-1 TO 3-1 SERICEA LESPEDEZA OR SWEET HAY WITH OVERSEEDED WEEPING 3 TONS/ACRE 3-4 LBS/ACRE SYMBOL WASTE MATERIALS LOVEGRASS
COMMON BERMUDA UNHULLED WITH MASTE MATERIAL SHALL NOT BE DISCHARGED TO WATERS OF THE STATE EXCEPT AS AUTHORIZED BY A SECTION 404 PERMIT. MANUFACTURERS' RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED ON SITE AND SITE PERSONNEL WILL BE MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES. 10 LBS/ACRE DISTURNED AREA STABLEATION (NITH MULCHING CHLY) ALL WASTE MATERIALS EXCEPT LAND CLEARING DEBRIS SHALL BE COLLECTED AND STORED IN A SECURELY LIDDED METAL DUMPSTER. THE DUMPSTER WILL MEET ALL LOCAL AND STATE SOLID WASTE MANAGEMENT REQUILATIONS. THE DUMPSTER WILL BE EMPTIED AS NEEDED AND THE TRASH WILL BE HAULED TO A STATE APPROVED LANDFILL ALL PRESONNEL WILL BE INSTRUCTED REAGABONG THE COMPRECT PROCEDURE FOR WASTE DEPOSAL NOTICES STATING THESE PROCEDES WILL BE POSTED AT THE CONSTRUCTION SITE BY THE CONSTRUCTION SUPERINITENDED'T, THE NOMINOUAL WHO MANAGES THE DAY-TO-DAY SITE OPERATIONS, MILL BE RESPONSIBLE TOR SEGING THAT THESE PROCEDURES ARE FOLLOWED. Ds1 CONTROLS Dall 3-1 TO 8-15 WEEPING LOVEGRASS AND VIRGATA OR SERICEA LESPEDEZA SCARIFIED 3-4 LBS/ACRE 40-60 LBS/ACRE THIS PLAN UTILIZES BEST MANAGEMENT PRACTICES TO CONTROL EROSION AND TURBUITY CAUSED BY STORM WATER RUN OFF, AN EROSION AND TURBUITY PLAN HAS BEEN PREPARED TO INSTRUCT THE CONTRACTOR ON PLACEMENT OF THESE CONTROLS. IT IS THE CONTRACTORS RESPONSIBILITY TO INSTALL AND MAINTAIN THE CONTROLS PER PLAN AS WELL AS ENSURING THE PLAN IS PROVIDING THE PROPER PROTECTION AS REQUIRED BY FEDERAL, STATE AND LOCAL LAWS. REFER TO "CONTRACTORS RESPONSIBILITY" FOR A VERBAL DESCRIPTION OF THE MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MITERIAL STORMOE AREA ON—SIE EQUIPMENT AND MATERIALS WILL INCUSE, DOGGLES, BUT FORS, MOPE, RAISS, GLOVES, GOOGLES, LIQUID ABSORBENT (I. KITTY LITTER OF EQUAL), SAND, SANDUST, AND PLASTIC AND METAL TRASH CONTAINERS SPECIFICALLY FOR THIS PURPOSE. 4-1 TO 6-15 COMMON BERMUDA HULLED WITH WHITE DUTCH CLOVER AND PENSACOLA BANIA 4 LBS/ACRE 6 LBS/ACRE 50 LBS/ACRE Ds2 DISTURBED
ANEA
SEVELIZATION
(BITH
TEMPORATY
SEEDING) De2 60% CRIMSON CLOVER (TRIFOLIUM INCARRETUM) AND 30% KENTUCKY 31 FESCUE (FESTUCA ARUNDINACEA) OR KENTUCKY 31 FESCUE WITH RYE GRASS 10 LBS/1000 SQ.FT. 8-15 TO 11-15 ALL SPILLS WILL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY. THE SPILL AREA WILL BE KEPT WELL VENTILATED AND PERSONNEL WILL WEAR APPROPRAT PROTECTIVE CLOTHING TO PREVENT INJURY FROM CONTACT WITH A HAZARDOUS SUBSTANCE. DISTURBED
APEA
STABLIZATION
(BITH
PERMANENT
YESETATION) Ds3 HAZARDOUS WASTE 50 LBS/ACRE 15 LBS/ACRE 0x3 ALL HAZARDOUS WASTE MATERIALS WILL BE DISPOSED OF IN THE MANNER SPECIFIED BY LOCAL OR STATE REGULATION OR BY THE MANUFACTURER. SITE PERSONNEL WILL BE INSTRUCTED IN THESE PROCITICES AND THE SITE SUPERINTENDENT, IT BIOMODUAL WHO MANAGES DAY-TO-DAY SITE OPERATIONS WILL BE RESPONSIBLE FOR SEEDIN THAT THESE PRACITICES ARE FOLLOWED. STORM WATER MANAGEMENT SPILL OF TOXIC OR HAZARDOUS MATERIAL WILL BE REPORTED TO THE APPROPRIATE STATE OR LOCAL COMERNMENT AGENCY, RECARDLESS OF THE SIZE OF THE SPILL THE SPILL PREVENTION PLAN WILL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT THIS TYPE OF SPILL FROM RECOCURRING AND HOW TO CLEAN UP THE SPILL IF THERE IS AMOTHER ONE. A DESCRIPTION OF THE SPILL WHAT CAUSED IT, AND THE CLEANUP MEASURES WILL ALSO BE INCLUDED. FERTILIZER (12-4-8): 1500 LBS/ACRE AGRICULTURAL LIME: 2 TONS/ACRE MULCH: 2.5 TONS/ACRE BEFORE SPREADING SEED, THE TOPSOIL SHALL BE PULVERIZED TO A DEPTH OF TWO INCHES WITH EQUIPMENT CAPABLE OF OBTAINING PROPER PULVERIZATION OF THE SOIL. APPLY LIMESTONE AND FERTILIZER AND INCORPERATE INTO THE TOP TWO INCHES OF SOIL. AFTER SEED IS APPLIED, A ONE INCH LAYER OF WHEAT STRAW SHALL BE USED TO COVER ENTIRE SEEDED AREA (1 BALE/1000 SQ.FT.). SATURATE AREA WITH A FINE SPRAY OF WAITER. THE CONTRACTOR SHALL AT A MINIMUM IMPLEMENT THE CONTRACTOR'S REQUIREMENTS OUTLINED BELOW AND THOSE MEASURES SHOWN ON THE EROSION AND TURBORY CONTROL PLAN. IN ADDITION THE CONTRACTOR SHALL UNDERTAKE ADDITIONAL MEASURES REQUIRED TO BE IN COMPLIANCE WITH APPLICABLE PERMIT CONDITIONS AND STATE WATER QUALITY STANDARDS, DEPENDING ON THE NATURE OF MATERIALS AND METHODS OF CONSTRUCTION THE CONTRACTOR MAY BE Sai SEDMENT BARRER (NOICHE TIPE) ALL SANITARY WASTE WILL BE COLLECTED FROM THE PORTABLE UNITS AS NEEDED TO PREVENT POSSIBLE SPILLAGE. THE WASTE WILL BE COLLECTED AND DEPOSED OF IN ACCORDANCE WITH STATE AND LOCAL WASTE DISPOSAL REGULATIONS FOR SANITARY SEWER OR SEPTIC SYSTEMS. THE SITE SUPERINTENDENT RESPONSIBLE FOR THE DAY-TO-DAY SITE OPERATIONS, WILL BE THE SPILL PREVENTION AND CLEANUP COORDINATOR. HE/SHE WILL DESIGNATE AT LEAST ONE OTHER SITE PREPONDINL WHO WILL RECEASE SPILL PREVENTION AND CLEANUP TRANNIC. THESE INDIVIDUALS WILL EACH BECOME RESPONSIBLE FOR A PARTICULAR PHASE OF PREVENTION AND CLEANUP. THE MASES OF RESPONSIBLE SHALL PERSONNEL WILL BE POSTED IN THE MATERIAL. **34** TEMPCRORY SEDMENT OFFSITE VEHICLE TRACKING REQUIRED TO ADD FLOCCULANTS TO THE RETENTION SYSTEM PRIOR TO PLACING THE SYSTEM INTO OPERATION. TEMPORARY SEED: 3-1 TO 8-15 WEEPING LOVEGRASS (4-6 LBS/ACRE) 8-16 TO 12-31 RYE GRASS (40-50 LBS/ACRE) A STABILIZED CONSTRUCTION ENTRANCE WILL BE PROVIDED TO HELP REDUCE VEHICLE TRACKING OF SEDIMENTS, THE PAYED STREET ADJUCENT TO THE SITE ENTRANCE WILL BE SWEPT DAILY TO REJOVE ANY EXCESS MAJ, DIRT OR ROCK TRACKED FROM THE SITE DUMP TRUCKS HAULING MATERIAL, FROM THE CONSTRUCTION SITE WILL BE COVERED WITH A TARPAULIN. Ss STORAGE AREA AND IF APPLICABLE, IN THE OFFICE TRAILER ONSITE CONTROLS EROSION NOTES:

1. Stripping of vegetation, regrading, and other development activities shall be conducted in such a manner so as to minimize erosion.

2. Whenever feasible, natural vegetation shall be retained, protected, and supplemented.

3. The disturbed area and the duration of exposure to erosive elements shall be kept to a practicable minimum.

5. The disturbed area and the duration of exposure to erosive elements shall be kept to a practicable minimum.

6. The disturbed area and the duration of exposure to erosive elements shall be kept to a practicable minimum.

7. Permonent vegetation or mulching shall be employed to protect exposed critical areas during development.

7. Permonent vegetation and structural erosion control measures shall be installed as soon as practicable.

8. To the extent necessory, sediment in run-off water shall be tropped by the use of debris basins, slit trops, or similar measures until the disturbed area is stabilized area of the destruction of the stabilized area of any source of sediments and adequate sedimentation control facilities to retain sediments on sits or preclude sedimentation of adjocent veters beyond the levels specified in the permit.

1. Land disturbing activities shall not be conducted within treative-five (20) feat of the basins of any State valuras.

1. The contractor shall be expecially attentive to weather forecast to take every recaution and measures to protect disturbed areas in the event of bod weather. IT IS THE CONTRACTORS RESPONSIBILITY TO IMPLEMENT THE EROSION AND TURBUITY CONTROLS AS SHOWN ON THE EROSION AND TURBUITY CONTROLS. AS SHOWN ON THE EROSION AND TURBUITY CONTROL PLAN. IT IS ALSO THE CONTRACTORS RESPONSIBILITY TO ENJERT THESE CONTROLS ARE PROPERLY INSTALLED, MAINTAINED AND FUNCTIONING PROPERLY OF PREVENT TURBUITY ON THE EROSION AND TURBUITY CONTROLS SHOWN ON THE EROSION AND TURBUITY CONTROL READ AND AND TURBUITY CONTROL READ AND AND TURBUITY CONTROL READ AND AND TURBUITY CONTROL READ FOLIABLE FOLIABLE FOLIABLE STATE AND LOCAL EROSION AND TURBUITY CONTROL REQUIREMENTS. THE FOLIABLE SHOW BEST MANAGEMENT PRACTICES WILL BE IMPLEMENTED BY THE CONTRACTOR AS REQUIRED BY THE EROSION AND TURBUITY CONTROL PLAN AND AS REQUIRED TO MEET THE EROSION AND TURBUITY REQUIREMENTS IMPOSED ON THE PROJECT SITE BY THE REGULATIONY ADMINISTRATIVE CONTROL PLAN AND AS REQUIRED TO MEET THE EROSION AND TURBUITY REQUIREMENTS IMPOSED ON THE PROJECT SITE BY THE REGULATIONY ADMINISTRA B. SAMPLE TYPE. ALL SAMPLING SHALL BE COLLECTED BY "CRAB SAMPLES" AND THE ANALYSIS OF THESE SAMPLES MUST BE CONDUCTED IN ACCORDANCE WITH METHODOLOGY AND TEST PROCEDURES ESTABLISHED BY 40 CFR PART 136 (UNLESS OTHER TEST PROCEDURES HAVE BEEN APPROVED); THE GUIDANCE DOCUMENT TITLED "NPDES STORM WATER SAMPLING GUIDANCE DOCUMENT, EPA 633-B-92-001" AND GUIDANCE DOCUMENTS THAT MAY BE SPILL PREVENTION MATERIAL MANAGEMENT PRACTICES PREPARED BY THE EPD.

SAMPLE CONTAINERS SHOULD BE LABELED PRIOR TO COLLECTING THE SAMPLES.

SAMPLES SHOULD BE WELL MIXED BEFORE TRANSFERRING TO A SECONDARY CONTAINER.

LARGE MOUTH, WELL CLEANED AND RINSED CLASS OR PLASTIC JARS SHOULD BE USED FOR COLLECTING SAMPLES. THE JARS SHOULD BE CLEANED THOROUGHLY TO AVOID THE FOLLOWING ARE THE MATERIAL MANAGEMENT PRACTICES THAT WILL BE USED TO REDUCE THE RISK OF SPILLS OR OTHER ACCIDENTAL EXPOSURE OF MATERIALS AND SUBSTANCES TO STORM WATER RUNOFF. GOOD HOUSEKEEPING MANUAL, AUTOMATIC OR RISING STAGE SAMPLING MAY BE UTILIZED. SAMPLES REQUIRED MANUAL, AUTOMATIC OR RISING STAGE SAMPLING MAY BE UTILIZED. SAMPLES REQUIRED BY THIS PERMIT SHOULD BE ANALYZED IMMEDIATELY, BUT IN NO CASE LATER THAN 48 HOURS AFTER COLLECTION. HOWEVER, SAMPLES FROM AUTOMATIC SAMPLERS MUST BE COLLECTED NO LATER THAN THE NEXT BUSINESS DAY AFTER THEIR ACCUMULATION, UNLESS FLOW THROUGH AUTOMATED ANALYSIS IS UTILIZED. IF AUTOMATIC SAMPLING IS UTILIZ AND THE AUTOMATIC SAMPLER IS NOT ACTIVATED DURING THE QUALIFYING EVENT, THE PERMITTEE MUST UTILIZE MANUAL SAMPLING OR RISING STAGE SAMPLING DURING THE NEXT QUALIFYING EVENT, DILUTION OF SAMPLES IS NOT REQUIRED. SAMPLES MAY BE AMALYZED DIRECTLY WITH A PROPERLY CALIBRATED TURBIDIMETER. SAMPLES ARE NOT REQUIRED TO BE THE FOLLOWING GOOD HOUSEKEEPING PRACTICES WILL BE FOLLOWED ONSITE DURING THE CONSTRUCTION PROJECT. INVENTORY FOR POLLUTION PREVENTION PLAN AN EFFORT WILL BE MADE TO STORE ONLY ENOUGH PRODUCT REQUIRED TO d. Sampling Frequency.

(1). The primary permittee must sample in accordance with the Plan at least once for each rainfall event described below. For a qualifying event, the permittee shall sample at the beginning of any stormander discharge to a monitored receiving water and/or from as soon as possible.

(2). However, where manual and authandits compling are impossible (as defined in this permit), or are beyond the permittee's control, permittee shall take samples as soon as possible, but in no case more than twelve (12) hours ofter the beginning of the stormander do the job.

All materials stored onsite will be stored in a neat, orderly
Manner in their appropriate containers and, if possible, under a roof THE MATERIALS OR SUBSTANCES LISTED BELOW ARE EXPECTED TO BE PRESENT ONSITE DURING CONSTRUCTION: PRODUCTS WILL BE KEPT IN THEIR ORIGINAL CONTAINERS WITH THE ORIGINAL PRODUCTS WILL BE KEPT IN THEIR ORIGINAL CONTAINERS WITH THE ORIGINAL MANUFACTURES' LABEL
SUBSTANCES WILL NOT BE MICED WITH ONE ANOTHER UNLESS
RECOMMEDIDED BY THE MANUFACTURER.
WHENEVER POSSBILE, ALL OF A PRODUCT WILL BE USED UP BEFORE DISPOSING OF THE CONTAINER.
MANUFACTURER'S RECOMMENDATIONS FOR PROPER USE AND DISPOSAL WILL BE FOLLOWED.
THE STIE SUPERNITENDENT WILL INSPECT DAILY TO ENSURE MATERIALS ONSITE RECEIVE PROPER USE AND DISPOSAL. Masonry Blocks (2). However, where manual and automatic sampling are impossible to the more than twelve (12) hours after the beginning of the stormware permittee shall take samples as soon as possible, but in no case more than twelve (12) hours after the beginning of the stormware permittee shall cour for the following qualifying events are considered. (3). Sampling by the permittee shall cour for the following qualifying events are defined in this permit after all clearing and grubbing operations have been completed, but prior to completion of mass grading operations, in the drainage area of the location selected as the sampling locations that the sampling location which is selected as the sampling location which were considered, but prior to submitted for a NOT, in the drainage area of the location selected as the sampling location whichever comes first (c). At the time of sampling performed pursuant to (a) and (b) above, if BMPs in any area of the state that discharges for more controlled and maintained, corrective action shall be defined and implemented within two (2) business days, and turiedly samples shall be taken from discharges from that area of the site for each subsequent rain event that reaches or exceeds 0.5 inch during control in the sample shall be defined and an electrically shall be defined and an electrical shall be activated. On an unit pace-torm event inspections determine that BMPs are properly designed, installed and mointained.

(d). Where sampling pursuant to (a), (b) or (c) clove is required but not possible for not required because there was not discharge), the permittee, in occordance with Port ND.A.A.(d), must include a written justification in the inspection sport of why sampling was not performed. Providing this ju □ Cleaning Solvents
 □ Roofing Materials COOLED.

SAMPLING AND ANALYSIS OF THE RECEIVING WATER(S) OR OUTFALLS BEYOND THE MINIMUM PREQUENCY STATED IN THIS PERMIT MUST BE REPORTED TO EPD AS SPECIFIED. □ Concrete Petroleum Based Products IN PART IVE.

SEMBIT AND EROSON CONTROL NOTES

1. ALL DESCON CONTROL MEASURES MPLDMENTD SHALL CONFORM TO THE CURRENT EDITION OF THE MANUAL FOR EROSION AND SEDMENT CONTROL IN GEORGIA, AND THE SOLIN AND DESCON CONTROL MEASURES MPLDMENTD SHALL CONFORM TO THE CONTROL CONTROL OF THE PROPERTY OF THE SOLIN AND THE CONTROL OF T \Box \Box . OWNER'S / OPERATOR'S CERTIFICATION (1) "I CERTIFY THAT THE RECEIVING WATER(S) OR THE OUTFALL(S) OR A COMBINATION OF BOTH WILL BE MONITORED IN ACCORDANCE WITH THE EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN." HAZARDOUS PRODUCTS (2) "I CERTIFY THE EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN (PLAN §) HAS BEEN PREPARED IN ACCORDANCE WITH PART IV OF THE GENERAL NPDES PERMIT GAY 100003, THE PLAN WILL BE IMPLEMENTED, AND THAT SUCH PLAN WILL PROVIDE FOR COMPLIANCE WITH THIS PERMIT." THESE PRACTICES ARE USED TO REDUCE THE RISKS ASSOCIATED WITH HAZAROUS MATERIALS.

RESPONDENCY SHILL BE KEPT IN ORIGINAL CONTAINERS UNLESS THEY ARE NOT EXCHANGED THE RESPONDENCY OF THE CONSIDERATION AND CONTROLLED A VARIOUS STACES OF CONSTRUCTION. ANY DIFFICULTY IN CONTROLLING ENGINED PLANARY PRODUCTION IS SECURITY.

6. THE CONTROLLING SHALL MAKENET PRODUCT CONTROL MEASURES URTE. PERMANENT VEGETATION IS ESTABLISHED. PERMANENT VEGETATION IS EXPLAINED.

6. THE CONTROLLING SHALL MAKENET PRODUCT CONTROLLING PROGRAMS OF DEACH DESIGNED. AND RESIDENT MAKENET. THE PRODUCT OF THE CHAPACT OF THE ADMINISTRATION AND ADMI (3) "I CERTIFY UNDER THE PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTICHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED THE ASSURE HIM GUNLED PESSOR OF A STATE OF THE PERSON OR PERSON WHO MANAGE THE SYSTEM, OR THOSE PERSON DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION, THE INFORMATION SUBMITTED IS TO THE BEST OF MY INDUILEDGE AND BELIFF, TRUE, ACCUMENT AND COMPLETE. I AM MARKE THAT THERE ARE SOMERICANT PROMITED FOR SUBMITTING TASES INFORMATION, INCLUDING THE POSSIBILITY OF FINE AN IMPRISONMENT FOR KNOWING VOLCITIONS. and (a). Existing construction activities, i.e., those that are occurring on the bards the distribution of PRODUCT SPECIFIC PRACTICES
THE FOLLOWING PRODUCT SPECIFIC PRACTICES WILL BE FOLLOWED ON-SITE:
PEROLUM PROPUCTS ALL ON-SITE VEHICLES WILL BE WONTORED FOR LEAKS
AND RECEIVE REQULAR PREVENTIVE MAINTENANCE TO REDUCE THE CHANCE OF
LEAKAGE, PETROLEUM PRODUCTS WILL BE STORED IN TIGHTLY SPELED CONTAINERS
WHICH ARE CLEARLY LUBELED. MY ASPHALT SUBSTANCES USED ON-SITE WILL BE
APPLIED ACCORDING TO THE MAINTFACTURER'S RECOMMENDATIONS. (4) I CERTIFY THAT THE PERMITTE'S EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN PROVIDES FOR AN APPROPRIATE AND COMPREHENSIVE SYSTEM TO BEST MANAGEBENT PRACTICES REQUIRED BY THE GA WATER QUALITY CONTROL ACT AND THE DOCUMENT "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GA" (MANUAL) PUBLISHED BY THE STATE SOLS AND WATER CONSERVATION COMMISSION AS OF JANUARY 1 OF THE YEAR IN WHITCH LAND DISTURBING ACTIVITY WAS PERMITTED. THE PLAN PROVIDES FOR THE SAMPLING OF THE RECEIVING WATER OUTFALLS. THE RECEIVING WATER OF THE SAMPLING OF THE STORM WATER OUTFALLS. THE DESIGNED SYSTEM OF BEST MANAGEBENT PRACTICES AND SAMPLING METHOD IS DEPENDED SYSTEM OF BEST MANAGEBENT PRACTICES AND SAMPLING METHOD IS DEPENDED TO 100003. FEFTILIZERS
FERTILIZERS USED WILL BE APPLIED ONLY IN THE MINIMUM ANOUNTS
FECOMMENDED BY THE MANUFACTURER. ONCE APPLIED, FERTILIZER WILL BE
WORKED INTO THE SOIL TO LIMIT EXPOSURE TO STORM WATER. STORAGE WILL
BE IN A COVERED MERS. THE CONTENTS OF MAY PAYTILLY USED BAGS OF
FERTILIZER WILL BE TRANSFERMED TO A SEALABLE FRASTIC BIN TO A MOD SPILLS. APPENDIX1
a) During construction activities, double the width of the 25 foot undisturbed vegetated buffer along all State waters requiring a buffer. During construction activities, EPD will not grant variances to any such buffers that are increased in width.
b) Increase all temporary sediment basins and retrofitted storm water management basins to provide sediment storage of at least 3600 cubic feet (134 cubic yards) per acre drained.
c) Use baffles in all temporary sediment basins and retrofitted storm water management basins to at least double the conventional flow path length to the outlet structure.
d) A large sign (minimum 4 feet x 8 feet) must be posted on site by the actual start date of construction. The sign must be visible from a public roadway. The sign must identify the following: (1) construction site, (2) the permittee(s), (3) the contact person(s) and telephone number(s), and (4) the permittee-hosted website where the Plan can be viewed must be provided on the submitted NOI. The sign must remain on site and the Plan must be available on the provided website until a NOT has been submitted.

Les force(the NDPIES Repri) PAINTS
ALL CONTAINERS WILL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE, EXCESS PAINT WILL NOT BE DISCHARGED TO THE STORM SEWER SYSTEM BUT WILL BE PROPERLY DISPOSED OF ACCORDING TO MANUFACTURERS' INSTRUCTIONS OR STATE AND LOOK, REGULATIONS. telephone number(s), and (4) the permittee-hosted website where the Plan can be viewed must be provided on the submitted NOI. The sign must remain on site and the Plan must be available on the provided website until a NOT has tell use floculants or coagulants and/or mutch to stabilize areas left disturbed for more than seven (7) calder days in accordance with Section III. D.1. of the NPDES Permit.

§) Conduct turbidity sampling after every rain event of 0.5 inch or greater within any 24 hour period, recognizing the exceptions specified in Section IV.D.6.d. of the NPDES Permits.

§) Comply with the applicable end-of-pipe turbidity effluent limit, without the "BMP defense" as provided for in O.C.G. A. 12.7-6 (a)(1).

§) Reduce the total planned site disturbance to less than 50% impervious surfaces (excluding any State-mandated buffer areas from such calculations). All calculations must be included on the Plan.

§) Lemit the amount of disturbed area at any one time to no greater than 25 acres or 50% of the total planned site, whichever is less. All calculations must be included on the Plan.

§) Use "Dir! If techniques available on the EPD website to model and manage construction storm water off (fincluding sheet flow). All calculations must be included on the Plan.

§) Lamber of the PD website to model and manage construction storm water water (fincluding sheet flow) and calculations must be included on the Plan.

§) Use "Dir! If techniques available on the EPD website to model and manage construction storm water water (fincluding sheet flow) and calculations must be included on the Plan.

§) Use must be (5) I CERTIFY THAT THE APPLICABLE PORTIONS OF THE EROSION CONTROL PLANS WILL BE PROVIDED TO EACH SECONDARY PERMITTEE PRIOR TO THE SECONDARY PERMITTEE CONDUCTING ANY CONSTRUCTION ACTIVITY. CONCRETE TRUCKS CONCRETE TRUCKS WILL NOT BE ALLOWED TO WASH OUT OR DISCHARGE SURPLUS CONCRETE OR DRUM WASH WATER ON THE STE. Soil Cleanup. and Control Practices

Local, Stote and menufocular's recommended methods for spill cleanup will be clearly posted and procedures will be made ovailable to site personnel.

Material and adjustment necessary for spill cleanup will be largh in the moterial storage areas. Typical moterials and equipment notions, and the moterial storage areas. Typical moterials and equipment social spill Soil Cleanup and Control Practices OWNER / OPERATOR'S SIGNATURE INSPECTION / MAINTENANCE PROCEDURES INSPECTIONS BY A QUALIFIED PERSONNEL PROVIDED BY THE PRIMARY PERMITTEE AND THE ASSOCIATED RECORDS SHALL BE KEPT ON SITE IN COMPLIANCE WITH GAR. o) Install sod for a minimum 20 foot width (in lieu of seeding) after final grade has been achieved, along the site perimeter wherever storm water (including sheet flow) may be discharged. b) Todated social a strain social a strain strain as a section of the strain strain as a section (V.D.4.a.(3)(a) – (c); secondary permittees, Section IV.D.4.b.(3)(a) – (c); and tertiary permittees Section IV.D.4.c.(3)(a) – (c) * THE NOTICE OF INTENT AND NOTICE OF TERMINATION SHALL BE FILED WITH EPD AND CHEROKEE COLINITY IF APPLICABLE THE PROPERTY WAS THE WAS THE COSCIN PROFESSIONAL WAS PRESENTED THE PROPERTY OF permittees, Section IV.D.4.b.(3)(a) – (c); and tertiary permittees Section IV.D.4.c.(3)(a) – (c) 1) Apply the appropriate compost blankets (minimum depth 1.5 inches) to protect soil surfaces until vegetation is established during the final stabilization phase of the construction activity.

1) Substitution phase of the construction activity.

2) Use alternative BMPs whose performance has been documented to be superior to conventional BMPs as certified by a Design Professional (unless disapproved by EPD or the Georgia Soil and Water Conservation Commission). (If using this item please s) Use alternative BMP's whose performance has been documented to be superior to conventional BMPs as certified by a Design Professional (unless disapproved by EPD or the Georgia Soil and Water Conservation Commission). (It using this item please refer to the Atternative BMP guidance document found at www. gaswcc.georgia.gov)

() Limit the total planned site disturbance to less than 15% impervious surfaces (excluding any state mandated buffer areas from such calculations). All calculations must be included in the Plan.

u) Conduct inspections during the intermediate grading and drainage BMP phase and during the final BMP phase and during the final BMP phase and during the final BMP phase. The design professional who prepared the Plan in conduct inspections during the intermediate grading and drainage BMP phase and during the final BMP phase.

v) Install Post Construction BMPs (e.g., runoff reduction BMPs) which remove 80% TSS as outlined in the Georgia Stormwater Management Manual known as the Blue Book or an equivalent or more stringent design manual. Effective January 1, 2019* This ALL SAMPLING AND INSPECTION PROCEDURES SHALL BE DONE PER STATE OF GEORGA DEPARTMENT OF NATURAL RESOURCES ENVIRONMENTAL PROTECTION DMISION GENERAL PERMIT NO. GAR100003 AND "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA", CURRENT EDITION. The contractor shall notify the licensed professional who prepared this plan if more than 1320 gallons of petroleum is stored onalte (this includes copacities of equipment) or if any one piece of equipment has a capacity greater than 680 gallons. The contractor will need a Spill Prevention Containment and Countermeasures Plan prepared by that licensed professional. requirement is different for infrastructure projects Certified personnel for primary permittees shall conduct inspections at least once every founteen (14) calendar days and within 24 hours of the end of the storm that is 0.5 inches rainfall orgreater in accordance with Section IV.D.4.a.(3)(a) – (c) of this permit. MAINTANANCE OF ALL EROSION CONTROLS SHALL BE PER THE "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA", CURRENT EDITION. EACH SECONDARY PERMITTEE SHALL BE PROVIDED WITH A COPY OF THE REVISION PLANS OR PORTIONS OF THE PLAN APPLICABLE TO THE SITE AND EACH SECONDARY PERMITTEE SHALL SIGN THE PLAN OR PORTION OF THE PLAN APPLICABLE TO THERE SITE. ANY AMENDMENTS TO THE ESAPC PLAN WHICH HAVE A SIGNIFICANT EFFECT ON BIMPS WITH A HYDRAULC COMPONENT MUST BE CERTIFIED BY THE DESIGN PROFESSIONAL. SECONDARY PERMITTEES SIGN WHEN RECEIVING PLANS. ALL SECONDARY PERMITTEES MUST SUBMIT SECONDARY 14 DAYS PRIOR TO BEGINNING CONSTRUCTION ACTIVITY. FAX____ DESIGN PROFFESIONAL 7-DAY VISIT CERTIFICATION DATE OF INSPECTION ___ I CERTIFY THE SITE WAS IN COMPLIANCE WITH THE ESAPO PLAN ON THE DATE ON INSPECTION. GSWCC LEVEL IA CERTIFICATION NO. GSWCC LEVEL IA CERTIFICATION NO. _ GSWCC LEVEL V DESIGN PROFESSIONAL CERTICATION # INSPECTION REVEALED THE FOLLOWING DISCREPANCIES FROM THE ES&PC PLAN. THE DEFICIENCIES MUST BE ADDRESSED AND AN RE-INSPECTION SCHEDULED, WORK SHALL NOT PROCEED ON THE SITE UNTIL DESIGN PROFESSIONAL CERTIFICATION IS OBTAINED.

GSWCC LEVEL IA CERTIFICATION NO.

SWCC LEVEL IA CERTIFICATION NO. _

VEGETATIVE MEASURES DESCRIPTION Establishing temporary protection for disturbed erose where seedings may not know a sofistion ground account to produce an erosion relateding Distribing a temporary regulation cover with fact growing exactings on distribut areas. Establishing permanent vegetation over such as trees, alreide, vince, gracese, sed, or legames an additional series. STRUCTURAL MEASURES

A barfer to present sediment from leading the construction ofte. It may be construct, before of alter or hop, brash, logs and point, growd, or all large.

Waters Supporting Warm Water Fisheries

Surface Water Drainage Area, square miles

0-4.99 5-9.99 10-24.99 25-49.99 50-99.99 100-249.99 250-499.99 500+ 1.00-10 75 150 200 400 750 750 750 10.01-25 100 100 200 300 50 50 100 100 150 50.01-100 50 300 100.01+ 50 50 50 50 50

"I CERTIFY THAT THE PERMITTEE'S EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN PROVIDES FOR AN APPROPRIATE AND COMPREHENSIVE SYSTEM OF BEST MANAGEMENT PRACTICES REQUIRED BY THE GEORGIA WATER QUALITY CONTROL ACT AND THE DOCUMENT "MANUAL FOR QUALITY CONTROL ACT AND THE DOCUMENT "MANUAL FOR EROSION AND SEDIMENTATION CONTROL IN GEORGIA" (MANUAL) PUBLISHED BY THE STATE SOIL AND WATER CONSERVATION COMMISSION AS OF JANUARY 1 OF THE YEAR IN WHICH THE LAND DISTURBING ACTIVITY WAS PERMITTED," PROVIDES FOR THE SAMPLING OF THE STORM WATER OUTFALLS AND THAT THE DESIGNED SYSTEM OF SECTIMENT OF THE STORM WATER OUTFALLS AND THAT THE DESIGNED SYSTEM OF SECTIMENT PROFESSION OF THE STAMPLING OF THE STORM WATER OUTFALLS AND THAT THE DESIGNED SYSTEM OF BEST MANAGEMENT PRACTICES AND SAMPLING METHODS IS EXPECTED TO MEET THE REQUIREMENTS CONTAINED IN THE

I FURTHER CERTIFY UNDER PENALTY OF LAW THAT THIS PLAN WAS PREPARED AFTER A SITE VISIT TO THE LOCATIONS DESCRIBED HERE IN BY MYSELF OR MY AUTHORIZED AGENT, UNDER MY DIRECT SUPERVISION.



per the rian.

3. All written correspondence required by this permit shall be submitted by return receipt certified mail (or similar service) to the appropriate District Office of the EPD according to the schedule in Appendix A of this permit. The permittee shall retain a copy of the proof of submittal at the construction site or the proof of submittal shall be readily available at a designated location from commencement of construction until such time as a NOT is submitted in accordance with Part VI.

To Resemble 1. The primary permittee shall retain the following records at the construction site or the records shall be readily available at a designated alternate acceptance with Part VII.

1. The primary permittee shall retain the first of the present of the present of the permittee of the present of the permittee of the permittee of the present of the results of the inspection conducted in accordance with Part VII.5 of this permittee of the present of the permittee of the present of the permittee of the permittee of the present of the permittee of the present of the permittee of the permittee of the present of the permittee of the permittee

2. Copies of all Notices of Intent, Notices of Termination, Inspection, reports, sampling reports (including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation) or other reposits requested by the EPD, Erosian, Sadimentation, and Pollution that the property of the property of the property of the PD, Prosian, Sadimentation, and Pollution that the retained by the permittee who either produces or used it or a peried of or it least three years from the date that the NOT is submitted in accordance with Part VI, of this permit. These records must be maintained at the permittee sprimary place of business or at a designated attemative location once with Part VI, of this permit. These records must be maintained at the permittee sprimary place of business or at a designated attemative location once

I. Reporting.

1. The applicable permittees are required to submit the sampling results to the EPD at the address shown in Part ILC. by the fifteenth day of the month following the reporting period. Reporting periods are monthe during which samples are token in accordance with this permit. Sampling results end to in a clearly leighb format, Upon written notifications, PEP may require the applicable permittee to submit the sampling results on a more frequent basis. Sampling and analysis of any stormacter discharge(s) or the receiving sate(s) beyond the accordance with Part V.Q.2. Sampling reports must be submitted to EPD until such time as a NOT is submitted in accordance with Part V.Q.2. Sampling reports and include the following information:

2. All sampling reports shall include the following information:

3. The report of the careful of the permitted of the permitted of the permitted in accordance with Part V.Q.2. Sampling periods are considered to the permitted of the permi

neceurements;

The date(s) analyses were performed;

The time(s) analyses were initiated;

The time(s) analyses were initiated;

The name(s) of the certified personnel who performed the analyses;

References and written procedures, when available, for the analytical techniques or methods used;

The results of such analyses, including the bench sheets, instrument readouts, computer dista or topes, etc., used to determine these

serus; Results which exceed 1000 NTU shall be reported as "exceeds 1000 NTU;" and i. Certification statement that sampling was conducted as ar the Plan.

the construction octifyly has ceased at the permitted site. This period may be extended by request of the EPD at any time written notification to the permittee.

PRIMATY PERMITTEL/INSPECTIONS

(1). Each day when any type of construction activity has taken place at a primary permittee's site, certified personnel provided by the primary permittee shall inspect (a) all accessors the primary permittee's site where petrosum products are stored, used, or handled for spills and leaks from whiches and equipment and (b) all locations at the primary permittee's site where vehicles enter or suit the site for evidence of off-site sediment tracking. These inspections must be conducted until a Notice of Termitorion is submitted in the primary permittee's site where vehicles enter or suit the site for evidence of off-site sediment tracking. These inspections must be conducted until a Notice of Termitorion is submitted on the second report districts of the site of the second report districts with a second report districts of the site of the site of the site of the second report districts when the second report districts with the permit shall be representative of the monitored activity. Measurement of reinfall may be suspended if all provides of completes with this permit shall be representative of the monitored activity. Measurement of reinfall may be suspended if all areas of the site of a storm that is 0.5 inches ratified or greater (unless such storm ends ofter 550 PM on any friday or on any non-working Soturday, non-working Sunday or any non-working Search looking in which case the haspection shall be completed for the search shall be supported to the site of the site o

15) "NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50-FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTEL VEGETATION OR WITHIN 25-FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURDISDICTION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VAN

TO PERMITS.

8) THERE ARE NO BUFFER ENCROACHMENTS, THEREFORE, NO BUFFER VARIANCE IS REQUIRED.

7) "AMENDMENTS / REVISIONS TO THE ES & PC PLAN WHICH HAVE A SIGNIFICANT EFFECT ON BMP'S WITH A HYDRAULIC COMPONENT MUST BE CERTIFED BY

PROFESSIONAL."

10. "WASTE MATERIALS SHALL NOT BE DISCHARGED TO WATERS OF THE STATE, EXCEPT AS AUTHORIZED BY SECTION 404 PERMIT"

10. "THE ESCAPE OF SEDMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDMENT CONTROL MEASURES AND PRACTICES PRIOR TO LAND DISTURBENG ACTIVITIES."

20. "EXOSION CONTROL MEASURES WILL BE MANTANED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROMDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL MEASURES WILL BE MANTANED TO CONTROL OR TREAT THE SEDMENT SOURCE."

21) "ANY DISTURBED AREA LETT EXPOSED FOR A PERIOD GREATER THAN 7 DAYS SHALL BE STABLIZED WITH MULCION OR TEMPORARY SEEDING."

22) For building moterfale, building products, construction vestes, trash, knotecope materials, efficient, pesticides, herbiddes, detergents, conflarny weste and other materials present on the alte, provide cover (e.g. pleatic sheating, temporary roofs) to minimize the exposure of these products to precipitation and to stormworter, or a similarly effective mean designed to minimize the conflarner of pollutarity or these products of the provided of the provid

EROSION CONTROL NOTES

CHEROKEE 2

LOCATED IN LAND LOT(S): 592 DISTRICT - 15, SECTION - 2


CHEROKEE COUNTY, GEORGIA PREPARED: DEC. 27, 2019


SCALE: N/A


BY: WIKLE LAND SURVEYING, F P.O. BOX 1164 CANTON, GEORGIA 30169 PHONE: (770) 479-8364 479-8364 -- MEMBER --SURVEYING AND MAR

SOCIETY OF GEORGI

SHEET 9 OF 23 SHEETS









STONE SIZE: 1.5" TO 3.5" DIAMETER


MAY REQUIRE PERIODIC TOP DRESSING WITH 1.5"-3.5" STON

MAINTAIN IN A CONDITION THAT WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC ROADS

PAD THICKNESS IS 6" MINIMUM







(St) RIPRAP OUTLET PROTECTION

NOTES:

1. La IS THE LENGTH OF THE RIPRAP APRON.

2. D = 1.5
TIMES THE MAXIMUM STONE DIAMETER BUT NOT LESS

3. IN A WELL-DEFINED CHANNEL, EXTENT THE APRON UP THE CHANNEL BANKS TO AN ELEVATION OF E

ELEVATION OF 6"
ABOVE THE
MAXIMUM

PIPE OUTLET TO FLAT AREA -- NO WELL DEFINED CHANNEL

SECTION A-A

FILTER BLANKET


OR TO THE TOP OF

PIPE OUTLET TO WELL DEFINED CHANNET (BENEVAL)

RIPRAP APRON


RIPRAP


PLAN





A LARGE SIGN (MINIMUM 4 FEET X 8 FEET) MUST BE POSTED ON SITE BY THE ACTUAL START DATE OF CONSTRUCTION. THE SIGN MUST BE VISIBLE FROM A PUBLIC ROADWAY, THE SIGN MUST IDENTIFY THE FOLLOWING: (1) CONSTRUCTION SITE, (2) THE PERMITTEE(S), (3) THE CONTACT PERSON(S) AND TELEPHONE NUMBER(S), AND (4) THE PERMITTEE-HOSTED WEBSITE WHERE THE PLAN CAN BE VIEWED MUST BE PROVIDED ON THE SUBMITTED NOI. THE SIGN MUST REMAIN ON SITE AND THE PLAN MUST BE AVAILABLE ON THE PROVIDED WEBSITE UNTIL A NOT HAS BEEN SUBMITTED.

EROSION CONTROL SIGN DETAIL









I FURTHER CERTIFY UNDER PENALTY OF LAW THAT THIS PLAN WAS PREPARED AFTER A SITE VISIT TO THE LOCATIONS DESCRIBED HERE IN BY MYSELF OR MY AUTHORIZED AGENT, UNDER MY DIRECT SUPERVISION.



PLAT PREPARED: DEC. 27, 2019 SCALE: 1" = 20'

EROSION DETAILS FOR:

CHEROKEE 2

LOCATED IN LAND LOT(S): 592

DISTRICT - 15. SECTION - 2


CHEROKEE COUNTY, GEORGIA

P.O. BOX 1164 CANTON, GEORGIA 30169 PHONE: (770) 479-8364 -- MEMBER --

SOCIETY OF GEORGIA

RON R. WIKLE JR. PLS 2578 CERTIFIED DESIGN PROFESSIONAL CERTIFICATION No.0000000178 SHEET

10 OF 23 SHEETS



SHEET 11 OF 23 SHEETS

General Notes:

- 1. Contractor shall have underground utilities located, legibly marked and is responsible for repairs, any and all damages which may occur as a result of landscape installation.
- All plants shall be inspected prior to installation.
 All plants are subject to the approval of the owner
- before, during and after installation.

 4. The Cherokee County Aroborist must approve any alterations or revisions to the landscape sketch.
- 5. The contractor shall protect existing features on site. 6. All planting areas and unpaved areas on site, must
- be completely mulched as specified.
 7. The Landscape contractor shall verify all quantities.
 8. This Plan is not for use as a Detailed Landscaping Plan, rather an over all location including Tree Replacement and/or Tree Save Area along with areas
- reserved for Landscaping as needed for Land Disturbance Activities and Permitting.


 9. A minimum of three (3) species shall be planted (no single species can account for >33 % of replanted trees if >10 trees are planted (Section 25.21)


Table B Conversion of Replacement Tree Caliper to Density Factor Units						
Caliper Size	Density Factor Units					
1"	NOT TO BE USED					
2"	0.4					
3"	0.5					
4"	0.7					
5"	0.9					
6"	1.0					
7"	1.2					
8"	1.3					
9"	1.5					
10"	1.7					


The values in table B shall also be used to determine the quantity of replacement trees needed for any Specimen Tree recompense planting. This planting is additional to planting required for Site Density requirements


"ALL TREE PROTECTION MEASURES MUST BE INSTALLED PRIOR TO CLEARING.


"NO TREES OR SHRUBS WILL BE INSTALLED IN THE RIGHT OF WAY ON PUBLIC ROADS OR IN THE ACCESS AND UTILITY EASEMENTS FOR PRIVATE STREETS." "CONTACT THE COUNTY ARBORIST FOR A SITE INSPECTION UPON COMPLETION OF LANDSCAPE INSTALLATION PRIOR TO ISSUANCE OF A CERTIFICATE OF OCCUPANCY."
























TREES ARE TO BE A MINIMUM OF 6' TALL AT THE TIME OF PLANTING

TREE SAVE DETAILS


CHEROKEE 2


LOCATED IN LAND LOTS: 592 DISTRICT - 15 SECTION - 2 CHEROKEE COUNTY, GEORGIA PREPARED: DEC. 27, 2019


SHEET 12 OF 23 SHEETS





SHEET 13 OF 23 SHEETS













PROJECT- GLEN NEDZA - CHEROKEE COUNTY, GA
SPECIFIER: JIM SARVER
AGENT: STEPHANIE RONDEAU- EGI ASSOCIATES
CALCULATIONS BY BENJAMIN PEIRICK- PHILLIPS LIGHTING
DATE: MARCH 25, 2021
SCALE: 1:1
LUMEN VALUES ARE BASED ON TESTS PERFORMED IN COMPLIANCE WITH IESNA LM-79
PT. X VALUES SHOWN ARE HORIZONTAL ILLUMINANCE AT GRADE (SINGLE-PLANE, IN FOOTCANDLES
THE 0.85 LLF IS BASED ON THE MEAN LUMENS OF THE L70 OR 70% DEPRECIATION OF INTIAL OUTPUT.
FIELD PERFORMANCE WILL DEPEND ON AMBIENT TEMPERATURE, ELECTRICAL AND SITE CHARACTERISTICS
LUMINAIDE LEICHT CHOWN IS ADDOVIMATE OVEDALL MOLINTING LEICHT ADOVE SINGILED COADE (LING)

STATISTICAL AREA SUMMARY							
PROJECT: GLEN NEDZA - CHEROKEE							
LABEL	MIN	AVG	MAX	AVG/MIN	MAX/MIN	# PTS	UNITS
PARKING AREA	0.4000	0.5400	5	3.8500	12.5000	297	FC

	LUMINAIRE SCHEDULE								
	PROJECT: GLEN NEDZA - CHEROKEE COUNTY								
SYMBOL	QTY	LABEL	DESCRIPTION	ARRANGMENT	LUM. LEMENS	LLF	FILE NAME		
A	4	W3	GARDCO 161-3-150LA-6470-NW	SINGLE	12466	0.850 0	161-3-150LA-6470-N W.IES		
В	3 W3		GARDCO 161-3-150LA-6470-NW	SINGLE	12087	0.850 0	161-4-150LA-6470-N W.IES		





GENERAL

- 1. NO PROVISION OF ANY REFERENCED STANDARD SPECIFICATION, MANUAL OR CODE (WHETHER OR NOT SPECIFICALLY INCORPORATED BY REFERENCE IN THE CONTRACT DOCUMENTS) SHALL BE EFFECTIVE TO CHANGE THE DUTIES AND RESPONSIBILITIES OF OWNER, CONTRACTOR, DESIGN PROFESSIONAL, SUPPLIER, OR ANY OF THEIR CONSULTANTS, AGENTS, OR EMPLOYEES FROM THOSE SET FORTH IN THE CONTRACT DOCUMENTS. NOR SHALL IT BE EFFECTIVE TO ASSIGN TO THE DESIGN PROFESSIONAL OF RECORD OR ANY OF THE DESIGN PROFESSIONAL OF RECORD'S CONSULTANTS, AGENTS, OR EMPLOYEES ANY DUTY OR AUTHORITY TO SUPERVISE OR DIRECT THE FURNISHING OR PERFORMANCE OF THE WORK OR ANY DUTY OR AUTHORITY TO UNDERTAKE RESPONSIBILITIES CONTRARY TO THE PROVISIONS OF THE CONTRACT DOCUMENTS.
- 2. CONTRACT DOCUMENTS INCLUDE, BUT ARE NOT LIMITED TO, THE STRUCTURAL DOCUMENTS (DRAWINGS AND SPECIFICATIONS), BUT DO NOT INCLUDE SHOP DRAWINGS, VENDOR DRAWINGS, OR MATERIAL PREPARED AND
- 3. REFERENCE TO STANDARD SPECIFICATIONS OF ANY TECHNICAL SOCIETY, ORGANIZATION, OR ASSOCIATION OR TO CODES OF LOCAL OR STATE AUTHORITIES, SHALL MEAN THE LATEST STANDARD, CODE, SPECIFICATION OR TENTATIVE SPECIFICATION ADOPTED AT THE DATE OF TAKING BIDS, UNLESS SPECIFICALLY STATED OTHERWISE.
- 4. CONTRACT DOCUMENTS SHALL GOVERN IN THE EVENT OF A CONFLICT WITH THE CODE OF PRACTICE OR SPECIFICATIONS OF ACI, PCI, AISC, SJI OR OTHER STANDARDS. WHERE A CONFLICT OCCURS WITHIN THE CONTRACT DOCUMENTS, THE STRICTEST REQUIREMENT SHALL GOVERN.
- 5. MATERIAL, WORKMANSHIP, AND DESIGN SHALL CONFORM TO THE REFERENCED BUILDING CODE.
- 6. CONTRACTOR SHALL COORDINATE THE STRUCTURAL DOCUMENTS WITH THE ARCHITECTURAL, MECHANICAL, ELECTRICAL, PLUMBING AND CIVIL DOCUMENTS. DESIGN PROFESSIONAL SHALL BE NOTIFIED OF ANY DISCREPANCY OR OMISSION. FOR DIMENSIONS NOT SHOWN ON THE STRUCTURAL DRAWINGS SEE THE ARCHITECTURAL DRAWINGS.
- 7. CONTRACTOR SHALL VERIFY EXISTING DIMENSIONS, ELEVATIONS, AND SITE CONDITIONS BEFORE STARTING WORK. DESIGN PROFESSIONAL SHALL BE NOTIFIED OF ANY DISCREPANCY.
- 8. CONTRACTOR HAS SOLE RESPONSIBILITY FOR MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES OF
- 9. THE STRUCTURE IS STABLE ONLY IN ITS COMPLETED FORM. TEMPORARY SUPPORTS REQUIRED FOR STABILITY DURING ALL INTERMEDIATE STAGES OF CONSTRUCTION SHALL BE DESIGNED, FURNISHED, AND INSTALLED BY THE
- 10. CONTRACTOR HAS SOLE RESPONSIBILITY TO COMPLY WITH ALL OSHA REGULATIONS.
- 11. ELECTRONIC DRAWING FILES WILL NOT BE PROVIDED TO THE CONTRACTOR. REPRODUCTION OF STRUCTURAL DRAWINGS FOR SHOP DRAWINGS IS NOT PERMITTED.
- 12. REVIEW OF SUBMITTALS OR SHOP DRAWINGS BY THE DESIGN PROFESSIONAL DOES NOT RELIEVE THE CONTRACTOR OF THE SOLE RESPONSIBILITY TO REVIEW AND CHECK ALL SUBMITTALS AND SHOP DRAWINGS BEFORE SUBMITTING TO THE DESIGN PROFESSIONAL. CONTRACTOR REMAINS SOLELY RESPONSIBLE FOR ERRORS AND OMISSIONS ASSOCIATED WITH THE PREPARATION OF SHOP DRAWINGS AS THEY PERTAIN TO MEMBER SIZES, DETAILS, AND DIMENSIONS SPECIFIED IN THE CONTRACT DOCUMENTS.
- 13. DETAILS LABELED "TYPICAL" ON THE STRUCTURAL DRAWINGS APPLY TO ALL SITUATIONS OCCURRING ON THE PROJECT THAT ARE THE SAME OR SIMILAR TO THE TYPICAL DETAILS UNLESS THOSE LOCATIONS ARE SPECIFICALLY DETAILED OTHERWISE.

CODE/DESIGN CRITERIA

- 1. STRUCTURE IS DESIGNED IN ACCORDANCE WITH THE FOLLOWING:
- INTERNATIONAL BUILDING CODE, 2018 EDITION, WITH GEORGIA AMENDMENTS

2. WIND LOADS:

■ 107 MPH BASIC WIND SPEED IMPORTANCE FACTOR = 1.00

3. EARTHQUAKE LOADS:

EXPOSURE B

- SEISMIC IMPORTANCE FACTOR: I = 1.00
- OCCUPANCY CATEGORY: B • SHORT PERIOD MAPPED SPECTRAL RESPONSE COEFFICIENT, $S_S = 0.2369$
- ■1 SECOND PERIOD MAPPED SPECTRAL RESPONSE COEFFICIENT, S1 = 0.0993
- SHORT PERIOD DESIGN SPECTRAL RESPONSE COEFFICIENT, SD_o = 0.253 ■1 SECOND PERIOD DESIGN SPECTRAL RESPONSE COEFFICIENT, SD1 = 0.159 SEISMIC DESIGN CATEGORY: C
- 4. UNLESS NOTED OTHERWISE CALCULATED INDIVIDUAL MEMBER DEFLECTIONS (IN INCHES) DO NOT EXCEED THE

DEAD LOAD L/360

DEAD + LIVE LOAD LIVE LOAD ROOF MEMBERS: FLOOR MEMBERS: L/360

• WHERE, L = SPAN LENGTH (IN INCHES) BETWEEN SUPPORTS. (FOR CANTILEVERS, L IS TWICE THE LENGTH OF THE CANTILEVER.) NOTE THAT THE TOTAL MAXIMUM CALCULATED FLOOR SYSTEM DEFECTION WILL BE THE SUM OF THE DEFLECTIONS OF THE SUPPORTED ELEMENTS IN A BAY.

5. NO PROVISIONS HAVE BEEN MADE FOR FUTURE HORIZONTAL OR VERTICAL EXPANSION.

FOUNDATION

- . ALL FOUNDATIONS SHALL BE INSTALLED UNDER THE GUIDANCE OF A REGISTERED PROFESSIONAL GEOTECHNICAL ENGINEER IN THE PROJECT STATE. THE GEOTECHNICAL ENGINEER SHALL GIVE CONSIDERATION TO THE TYPE OF BUILDING AND FOUNDATION LOADS INVOLVED AS WELL AS THE REQUIREMENTS OF THESE DOCUMENTS. DESIGN PROFESSIONAL IS NOT RESPONSIBLE FOR SUBSURFACE CONDITIONS ENCOUNTERED IN THE FIELD DIFFERENT TO
- 2. STRUCTURAL TESTING/INSPECTION AGENCY SHALL CERTIFY THE BEARING MEDIUM.
- 3. INDIVIDUAL SPREAD FOOTINGS AND CONTINUOUS FOOTINGS SHALL BEAR ON SOIL CAPABLE OF SUPPORTING 2000 PSF AND 2000 PSF, RESPECTIVELY.
- 3.1 NO FOOTINGS SHALL BEAR ON ROCK. UNDERCUT ROCK A MINIMUM OF 2 FEET BELOW BOTTOM OF FOOTING AND REPLACE WITH STRUCTURAL FILL.
- 4. FOUNDATION WALLS ARE DESIGNED FOR LATERAL PRESSURES DUE TO THE FOLLOWING EQUIVALENT FLUID DENSITIES:
- WALLS FREE TO DISPLACE AT TOP (ACTIVE CONDITION): 32.6 PCF
- 5. PROOF ROLL BUILDING AREAS WITH TWO COMPLETE COVERAGES OF A LOADED DUMP-TRUCK OR SCRAPER. REPLACE SOFT AREAS WITH COMPACTED STRUCTURAL FILL AS REQUIRED BY THE SPECIFICATIONS.
- 6. DENSIFY BUILDING AREAS AND A MINIMUM OF 15'-0" OUTSIDE THE BUILDING PERIMETER USING A VIBRATORY ROLLER (SEE SPECIFICATIONS).
- 7. UNDERCUT THE ENTIRE BUILDING AREA TO THE EXTENT SHOWN ON THE STRUCTURAL DOCUMENTS AND REPLACE WITH COMPACTED STRUCTURAL FILL AS REQUIRED BY THE SPECIFICATIONS.
- 8. STRUCTURAL FILL SHALL CONTAIN NO ORGANIC MATERIAL AND BE APPROVED BY A GEOTECHNICAL ENGINEER PRIOR TO PLACEMENT. STRUCTURAL FILL UNDER SLABS AND WITHIN 10'-0" OF THE BUILDING FOOTPRINT SHALL BE PLACED IN LIFTS OF THICKNESS DETERMINED BY THE INDEPENDENT TESTING AGENCY AND COMPACTED TO AT LEAST 95% OF ITS STANDARD PROCTOR MAXIMUM DRY DENSITY IN ACCORDANCE WITH ASTM D698. THE TOP 12" SUB-BASE UNDER SLABS ON GRADE SHALL BE COMPACTED TO AT LEAST 98% OF ITS STANDARD PROCTOR MAXIMUM DRY DENSITY. ALL BACKFILL, COMPACTION AND PROOF ROLLING OPERATIONS SHALL BE OBSERVED BY AN INDEPENDENT TESTING LABORATORY.
- 9. BACKFILL SHALL NOT BE PLACED AGAINST EXTERIOR OR RETAINING WALLS UNTIL THE WALLS HAVE ACHIEVED THEIR DESIGN STRENGTH AND THEIR LATERAL SUPPORT ELEMENTS ARE INSTALLED. PROVIDE ADEQUATE DRAINAGE AT BASEMENT AND RETAINING WALLS (SEE ARCHITECTURAL).
- 10. ALL FOOTINGS AND TURN DOWN SLAB EDGES SHALL PENETRATE TO A MINIMUM DEPTH OF 12" BELOW FINISHED GRADE.

REINFORCEMENT

- 1. REINFORCING STEEL SHALL CONFORM TO ASTM A615, GRADE 60, UNLESS NOTED OTHERWISE.
- 2. WELDED WIRE FABRIC SHALL CONFORM TO ASTM A185 AND HAVE MINIMUM SIDE AND END LAPS OF 8".
- 3. SUBMIT SHOP DRAWINGS WHICH ADEQUATELY DEPICT THE REINFORCING BAR SIZES AND PLACEMENT. WRITTEN DESCRIPTION OF REINFORCEMENT WITHOUT ADEQUATE SECTIONS, ELEVATIONS, AND DETAILS IS NOT ACCEPTABLE.
- 4. SPLICES SHALL BE CLASS B IN ACCORDANCE WITH ACI 318, UNLESS NOTED OTHERWISE. REINFORCEMENT SHALL BE SPLICED ONLY AT LOCATIONS SHOWN OR NOTED IN THE STRUCTURAL DOCUMENTS, EXCEPT REINFORCEMENT MARKED "CONTINUOUS" CAN BE SPLICED AT LOCATIONS DETERMINED BY CONTRACTOR, SPLICES AT OTHER LOCATIONS SHALL BE APPROVED IN WRITING BY THE DESIGN PROFESSIONAL.
- 5. REINFORCING STEEL DESIGNATED CONTINUOUS SHALL BE LAPPED AS FOLLOWS:
- CONCRETE REINFORCEMENT: CLASS B TENSION LAP
- 6. PROVIDE DOWELS FROM FOUNDATIONS THE SAME SIZE AND NUMBER AS THE VERTICAL WALL OR COLUMN REINFORCING, UNLESS NOTED OTHERWISE.
- 7. PLACE REINFORCEMENT AS FOLLOWS, UNLESS NOTED OTHERWISE:
- 7.1 CONCRETE REINFORCEMENT COVER
- EXPOSED TO EARTH OR WEATHER: UNFORMED CAST AGAINST EARTH 3" CLEAR FORMED #6 AND LARGER 2" CLEAR FORMED #5 AND SMALLER 1-1/2" CLEAR
- 8. ADHESIVE FOR REINFORCING DOWELS IN EXISTING CONCRETE SHALL CONFORM TO ASTM C881-02, TYPE IV, GRADE 3, CLASS A, B, & C EXCEPT GEL TIMES AND EPOXY CONTENT. ADHESIVE SHALL CONSIST OF A TWO COMPONENT ADHESIVE SYSTEM CONTAINED IN SIDE BY SIDE PACKAGING CONNECTEED TO A MIXING NOZZLE WHICH THOROUGHLY MIXES THE COMPONENTS AS IT IS INJECTED INTO THE HOLE. ADHESIVE SHALL HAVE PASSED ICC EVALUATION SERVICES, INC (ICC-ES) ACCEPTANCE CRITERIA 308 FOR LONG TERM CREEP. REINFORCING INSTALLED IN CONCRETE THAT MAY BECOME CRACKED UNDER SERVICE LOADS SHALL BE EVALUATED BY ICC-ES ACCEPTANCE CRITERIA 308 AND BE SPECIFICALLY APPROVED FOR USE IN CRACKED CONCRETE. CONTACT DESIGN PROFESSIONAL FOR DETERMINATION OF CRACKED OR UNCRACKED CONCRETE CONDITION UNLESS CONDITION IS NOTED ON THE DRAWINGS. INSTALL IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. MINIMUM EMBEDMENT LENGTH SHALL BE 12 BAR DIAMETERS, UNLESS NOTED OTHERWISE.
- 9. ALL DOWELS AND TERMINATING BARS SHALL HAVE A STANDARD 90 DEGREE HOOK.
- 10. ALL HORIZONTAL REINFORCING SHALL BE CONTINUOUS THROUGH CONTROL AND/OR CONSTRUCTION JOINTS

CAST-IN-PLACE CONCRETE

- 1. CONCRETE WORK SHALL CONFORM TO ACI 318 AND CRSI STANDARDS.
- 2. CONCRETE SHALL HAVE THE FOLLOWING MINIMUM SPECIFIED 28-DAY COMPRESSIVE STRENGTH:
- 2.1 NORMAL WEIGHT STRUCTURAL CONCRETE:

 FOOTINGS, PEDESTALS 3000 PSI RETAINING WALLS 4000 PSI

- 3. PIPES OR DUCTS SHALL NOT EXCEED ONE-THIRD THE SLAB OR WALL THICKNESS INCLUDING CROSSING UNLESS SPECIFICALLY DETAILED IN THE STRUCTURAL DOCUMENTS. ALL PIPES AND DUCTS SHALL BE PLACED IN THE MIDDLE THIRD OF THE SLAB OR WALL THICKNESS UNLESS SPECIFICALLY DETAILED OTHERWISE IN THE STRUCTURAL DOCUMENTS. SEE MECHANICAL AND ELECTRICAL DRAWINGS FOR LOCATION OF SLEEVES, ACCESSORIES, ETC.
- 4. REFER TO ARCHITECTURAL DRAWINGS FOR MOLDS, GROOVES, ORNAMENTS, CLIPS OR GROUNDS REQUIRED TO BE ENCASED IN CONCRETE.
- 5. CONSTRUCTION JOINT LOCATIONS SHALL BE APPROVED BY THE DESIGN PROFESSIONAL. NO HORIZONTAL CONSTRUCTION JOINTS ARE PERMITTED EXCEPT THOSE SHOWN ON THE STRUCTURAL DRAWINGS.
- 6. DEFECTIVE AREAS IN CONCRETE INCLUDING, BUT NOT LIMITED TO, HONEY-COMBING, SPALLS, AND CRACKS WITH WIDTHS EXCEEDING 0.016 INCH SHALL BE REPAIRED. EXTENT OF DEFECTIVE AREA TO BE DETERMINED BY THE DESIGN PROFESSIONAL
- 7. CONCRETE MIX DESIGN FOR 3000 PSI CONCRETE SHALL BE BASED ON A MAXIMUM AGGREGATE SIZE OF 1 IN. MAXIMUM WATER/CEMENT RATIO OF .58 FOR NON-AIR-ENTRAINED CONCRETE AND .46 FOR AIR-ENTRAINED CONCRETE AND A MAXIMUM SLUMP OF 4 IN. AIR ENTRAINED CONCRETE SHALL BE USED FOR EXTERIOR EXPOSED CONCRETE WITH AN AIR CONTENT BETWEEN 5.5 AND 7.5 PERCENT
- 8. CONCRETE SLABS ON GRADE SHALL NOT BE LOADED UNTIL A MINIMUM CONCRETE STRENGTH OF 1800 PSI HAS BEEN ATTAINED AND THE CONCRETE IS AT LEAST THREE DAYS OLD. ALL OTHER CONCRETE MEMBERS SHALL NOT BE LOADED UNTIL THE SPECIFIED CONCRETE DESIGN STRENGTH HAS BEEN ATTAINED
- 9. CONCRETE SHALL BE TESTED IN ACCORDANCE WITH ACI 301 AND THE SPECIFICATIONS FOR COMPLIANCE WITH THE CONTRACT DOCUMENTS. AT A MINIMUM CONCRETE SPECIMENS SHALL BE TAKEN FOR EVERY 100 YARDS OR PORTION THEREOF FOR EACH MIX DESIGN PLACED IN A DAY. CONCRETE TEST REPORTS SHALL BE AVAILABLE ON
- 10. C.J. ON THE SLAB AND FOUNDATION PLAN INDICATES A KEY-FORMED CONSTRUCTION JOINT OR SAW-CUT CONTROL JOINT IN THE CONCRETE SLAB ON GRADE. SAW-CUT CONTROL JOINTS SHALL BE INSTALLED WITHIN 12 HOURS OF SLAB PLACEMENT. CONTINUE REINFORCEMENT THROUGH JOINTS. CONSTRUCTION AND/OR CONTROL JOINTS SHALL BE SPACED NO FARTHER APART THAN 48 TIMES THE SLAB THICKNESS OC IN EACH DIRECTION CREATING PANELS WITH AN ASPECT RATIO NOT GREATER THAN 2:1.
- 11. UNLESS NOTED OTHERWISE, ALL REINFORCING SHALL BE CONTACT LAP SPLICED WITH A CLASS B SPLICE IN ACCORDANCE WITH ACI 318-05. FOR BARS WITH MINIMUM COVER AND SPACING GREATER THAN 2db AND 3db RESPECTIVELY, THE MINIMUM SPLICE LENGTH OF NOT LESS THAN 48db (db=BAR DIAMETER) SHALL BE USED. SPLICE LENGTHS SHALL BE INCREASED BY A FACTOR OF 1.3 FOR TOP REINFORCEMENT. LAP WELDED WIRE FABRIC (WWF) ONE SPACE PLUS 2 IN. ON ALL SIDES AT SPLICES.
- 12. ALL EXPOSED CORNERS OF CONCRETE SHALL HAVE A CHAMFER OR RADIUS OF 3/4", UNLESS NOTED OTHERWISE.
- 13. CONCRETE SHALL RECEIVE THE FOLLOWING FINISHES:
- EXTERIOR SLABS: BROOM FINISH IN DIRECTION OF SLOPE
- ALL OTHER CONCRETE: STEEL TROWEL FINISH
- 14. MAINTAIN CONCRETE AFTER PLACEMENT WITH MINIMAL MOISTURE LOSS AT RELATIVELY CONSTANT TEMPERATURE FOR THE PERIOD NECESSARY FOR HYDRATION OF CEMENT AND HARDENING OF CONCRETE (NOT LESS THAN 7 DAYS). COMPLY WITH THE REQUIREMENTS OF ACI 308- STANDARD PRACTICE FOR CURING CONCRETE: AMERICAN CONCRETE INSTITUTE. A COMBINATION CURING AND SEALING COMPOUND SHALL BE APPLIED AFTER THE CONCRETE HAS BEEN FINISHED OR THE FORMS REMOVED. COMPOUND SHALL MEET THE REQUIREMENTS OF ASTM

ENGINEER: Foresite Group, Inc. **o** | 770.368.1399 3740 Davinci Court f | 770.368.1944 Suite 100 Peachtree Corners, GA 3009 | www.fg-inc.net

DEVELOPER:

GLEN NEDZA 500 EAST MILL RD

GLEN NEDZA

CONTACT:

EROKE TION

REVISIONS

PROJECT MANAGER: DRAWING BY: JURISDICTION: 04/08/2021 DATE: SCALE: **VARIES** TITLE:

GENERAL NOTES

SHEET NUMBER:

COMMENTS:

JOB/FILE NUMBER:

1657.002

